


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 5 Twp. 9 Rge. 21 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW NE SW

Lease Owner Kansas Petroleum, Inc.
Lease Name Stephen Well No. 1
Office Address 500 Insurance Building, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed January 16 19 77
Application for plugging filed January 16 19 77
Application for plugging approved January 16 19 77
Plugging commenced January 16 19 77
Plugging completed January 16 19 77
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthzor
Producing formation Depth to top Bottom Total Depth of Well 3870
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud -pumped 70 sacks 50/50 Pozmix, 6% Gel thru drill pipe @ 1000'
Mud to 200' w/20 sacks cement thru drill pipe.
Mud to 40' w/ $\frac{1}{2}$ sack hulls plug and 10 sacks cement.

STATE RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1977
CONSERVATION DIVISION
Wichita, Kansas
1-21-77

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.
Larry Curtis (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis
Box 823, Great Bend, Kansas 67530
(Address)

My commission expires April 11, 1978



Clayton M. Hogue
Notary Public.

DRILLERS' WELL LOG

DATE COMMENCED: January 9, 1977
DATE COMPLETED: January 16, 1977

Kansas Petroleum, Inc.
"STEPHEN # 1"
NW NE SW
Sec 5-T9-R21W
Graham County, Kansas

ELEVATION: 2291 K.B.

0 - 16' Surface Soil
16 - 48' Post Rock
48 - 830' Shale
830 - 940' Sand
940 - 1175' Shale
1175 - 1218' Sand
1218 - 1771' Shale and Lime
1771 - 1830' Anhydrite
1830 - 1947' Shale
1947 - 2262' Shale and Shells
2262 - 3466' Shale and Lime
3466 - 3469' Shale
3469 - 3487' Lime and Shale
3487 - 3718' Lime
3718 - 3847' Lime and Shale
3847 - 3870' Dolomite
3870' RTD

FORMATION TOPS

Anhydrite 1771
Heebner 3466
Toronto 3487
Lansing K.C. 3505
Base K.C. 3718
Arbuckle 3847
RTD 3870

SURFACE PIPE:

Set used 8 5/8", 28# pipe
at 204' w/125 sacks Common,
2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1977
CONSERVATION DIVISION
Wichita, Kansas
121-77

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 18th day of January, 1977.

Dorothy M. Hagne
Notary Public



My Commission Expires: April 11, 1978