


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 8 Twp. 9S Rge. (E) 21 (W)
Location as "NE/CNW&SW" or footage from lines NE 1/4 NE 1/4 SW 1/4
Lease Owner Barnett Oil Company
Lease Name Swenson "B" Well No. 2
Office Address 417 First Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 16, 19 52
Application for plugging filed July 15, 19 52
Application for plugging approved July 15, 19 52
Plugging commenced July 15, 19 52
Plugging completed July 21, 19 52
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Arbuckle Depth to top 3834 Bottom 3875 Total Depth of Well 3875 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing		-0-	154	8 5/8"	154 ft.	None
Oil String		-0-	3874	5 1/2"	3874 ft.	2920 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

After setting oil string at 3874 feet cement was drilled out to 3870 feet and casing perforated for testing Arbuckle, after testing well was completed as a dry hole.
Casing filled with chat from 3870 feet to 3830 feet and 4 sacks of cement dumped on top of chat with dump bailer. Pipe shot off at 2920 feet and hole filled with heavy mud to 154 feet. Set rock bridge at 154 feet and filled surface casing with 15 sacks of cement to 107 feet. Filled surface casing with heavy mud from 107 feet to 35 feet and set rock bridge at 35 feet. Filled surface casing with cement from 35 feet to bottom of cellar.


RECEIVED
STATE CORPORATION COMMISSION
AUG - 9 1952
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Bert Self 8-9-52
Address 419 East Sixth St., Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Hunter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Hunter
417 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of August, 19 52
Mildred L. Willis
Notary Public.



PLUGGING
FILE SEC 8 T 9 R 214
BOOK PAGE 23 LINE 6

15-065-02315-00-00

BARNETT OIL COMPANY, ET AL
LOG OF SWENSON "B" WELL NO. 2
NE¹/₄ NE¹/₄ SW¹/₄ SECTION 8-9S-21W, GRAHAM COUNTY, KANSAS

DATE COMMENCED: May 20, 1952

DATE COMPLETED: June 16, 1952

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	30	
Sand	30	40	
Shale and Clay	40	55	
Sand	55	100	
Shale and Shells	100	154	Set 8 5/8" 24# Surface Pipe at 154 feet; cemented with 125 sacks of cement.
Shale	154	390	
Shale and Shells	390	1300	
Sand	1300	1535	
Shale and Shells	1535	1770	
Anhydrite	1770	1810	
Shale and Shells	1810	2520	
Shale and Lime	2520	2720	
Shale and Shells	2720	2830	
Shale and Lime	2830	3310	
Lime	3310	3350	
Lime and Shale	3350	3455	
Lime	3455	3765	
Lime and Shale	3765	3810	
Lime	3810	3875	Set 5 1/2" 15.50# Casing at 3874 feet; cemented with 125 sacks of cement. Perforated Arbuckle Lime with 24 shots from 3844 to 3854 feet and acidized with 500 gallons.
Total Depth		3875	Dry and Abandoned

CERTIFICATE

I, W. R. Hunter, Office Manager of Barnett Oil Company, certify that to the best of my knowledge and belief, the above is a true and correct log of the Swenson "B" Well No. 2 in the NE¹/₄ NE¹/₄ SW¹/₄ of Section 8-9S-21W, Graham County, Kansas.

W. R. Hunter

Subscribed and sworn to before me, a Notary Public, in and for the County of Sedgwick, State of Kansas, this 8th day of August, 1952.

Mildred F. Willis

 Notary Public.



Commission expires: February 27, 1956

RECEIVED
 CONSERVATION COMMISSION
 AUG - 9 1952
 CONSERVATION DIVISION
 Wichita, Kansas

8-9-52

PLUGGING
 FILE SEC-8-T-9-R-21W
 BOOK PAGE 33 LINE 6