


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-065-02333-00-00

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County, Sec. 8 Twp. 9S Rge. 21 (W)

Location as "NE/CNW/SW" or footage from lines A/C S/2 S/2 NW/4
Lease Owner Barnett Oil Company, Et Al
Lease Name Clack "B" Well No. 1
Office Address 411 First National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 24, 19 56
Application for plugging filed September 24, 19 56
Application for plugging approved September 25, 19 56
Plugging commenced September 24, 19 56
Plugging completed September 24, 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - - - - - 19 - -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3807 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	145'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 150'; set bottom plug at 150' with 1/2 sack of hulls on top of plug and 15 sacks of cement; filled hole to 30' with drilling mud; set top plug at 30' and wired with 1/2 sack of hulls on top of plug and cemented to bottom of cellar. Plugged rat hole with 2 sacks of cement.

(Well log attached)

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnett Drilling, Inc.
Address 409 First National Bank Bldg., Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
F. H. Rousey (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. H. Rousey
411 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of October, 19 56
My commission expires February 27, 1961



RECEIVED
OCT 4 X 1956
CONSERVATION DIVISION
Wichita, Kansas
10-4-56

RECEIVED
PLUGGING
FILE SEC 8 TWP 9S R 21W
BOOK PAGE 102 LINE 9
CONSERVATION DIVISION

15-009-02333-00-00

BARNETT OIL COMPANY
WELL LOG
CLACK "B" WELL NO. 1
A/C S/2 S/2 NW/4 SEC. 8-9S-21W
GRAHAM COUNTY, KANSAS

Date Started: 9-16-56
Date Completed: 9-24-56

<u>From</u>	<u>To</u>	<u>Formation</u>
0	20	Surface clay
20	30	Sand
30	145	Shale and Shells
145	760	Shale
760	1430	Sand and Shale
1430	1780	Shale and Shells
1780	1807	Anhydrite
1807	2100	Shale
2100	2300	Shale and Lime
2300	2800	Lime
2800	3515	Lime and Shale
3515	3807	Lime (Total Depth) (D. & A.)

Set 8 5/8", 24# s.s. casing at 145' with
125 sacks of cement.

PLUGGING			
FILE	SEC. 8	T 9	R. 21W
BOOK	PAGE 102	LINE 9	

10-2-56