

15-065-02468-00-00

THE DERBY OIL COMPANY
ET AL

Record of Well No. 1
Location: SW/c
Contractor: Glenn W. Peel
Drilling Commenced: 2-1-47
Elevation: 2272

Farm: Swenson
Sec. 8 Twp. 9 Rge. 21W
County: Graham
State: Kansas
Drilling Completed: 2-12-47

CASING RECORD

Set 8 5/8" Surface Casing @ 254' & cem. w/100 sx. by Halliburton

DRILLERS LOG

Formation	Bottom	Formation	Bottom
Sandy Clay	0- 55		
Shale & Shells	255		
Shale	450		
Sand & Shale	985		
Shale & Shells	1275		
Shale & Sand	1460		
Shale & Shells	1765		
Anhydrite	1805		
Shale & Shells	2260		
Lime	2375		
Lime & Shale Streaks	2520		
Lime & Shale	2600		
Lime	2665		
Shale & Lime	2780		
Lime & Shale Streaks	2895		
Shale & Lime	3050		
Shale	3076		
Lime	3125		
Lime & Shale	3225		
Lime	3790		
Conglomerate	3881		
Lime	3934		

GEOLOGICAL DATA

Tops:

Heebner	3443'
Lansing	3486'
BKC	3716'
Conglomerate	3785'
Arbuckle	3850'
Total Depth	3934'

Ran Schlumberger - no shows

D&A

INDEXED
MAR - 6 1947

3-6-47

PLUGGING
 FILE SEC 8 T 9 R 21W
 BOOK PAGE 98 LINE 5