

15-065-02543-00-00


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County. Sec. 8 Twp. 9S Rge. (E) 21 (W)

Location as "NE/CNW%SW%" or footage from lines. NW 1/4 SE 1/4 SW 1/4
Lease Owner Barnett Oil Company
Lease Name Swenson "B" Well No. 5
Office Address 417 First National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 21, 1954
Application for plugging filed April 21, 1954
Application for plugging approved April 21, 1954
Plugging commenced April 21, 1954
Plugging completed April 21, 1954
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3885 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing				8 5/8"	157'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 3885 feet to 155 feet. Set wooden plug at 155 feet and filled surface casing with 1/2 sack of hulls and 15 sacks of cement to 108 feet. Filled surface casing with heavy mud from 108 feet to 40 feet. Set second wooden plug at 40 feet and filled casing with 1/2 sack of hulls and 10 sacks of cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnett Drilling, Inc.
Address 623 First National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Hunter (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Hunter
417 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 12th day of May, 1954

My commission expires February 27, 1956.

Melroy J. Willis Notary Public.



PLUGGING
FILE SEC 8 T 9 R 21 W
BOOK PAGE 30 LINE 2

REL STATE CORP.
MAY 13 1954
CONSERVATION DIVISION
Wichita, Kansas
5-13-54

15-065-02543-00-00

BARNETT OIL COMPANY
LOG OF SWENSON "B" WELL NO. 5
NW $\frac{1}{4}$ SE $\frac{1}{4}$ SW $\frac{1}{4}$ SECTION 8-9S-21W
GRAHAM COUNTY, KANSAS

DATE COMMENCED: April 11, 1954

DATE COMPLETED: April 21, 1954

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sandy Clay	0	40	
Sandy Shale	40	100	
Shale	100	500	Set 8 5/8", 21# surface casing at 157'; cemented with 125 sacks of cement.
Shale and Shells	500	880	
Sand and Shale	880	1030	
Shale and Shells	1030	1275	
Sandy Shale	1275	1450	
Shale and Shells	1450	1610	
Shale	1610	1810	
Anhydrite	1810	1846	
Shale and Shells	1846	2245	
Shale	2245	2385	
Shale and Lime	2385	2520	
Lime	2520	2635	
Lime and Shale	2635	3560	
Lime	3560	3825	
Lime and Shale	3825	3885	
Total Depth		3885	Dry and Abandoned.

PLUGGING
 FILE SEC 8-T-9-R-21W
 BOOK PAGE 30 LINE 2

RECEIVED
 STATE CORPORATION COMMISSION

MAY 13 1954

CONSERVATION DIVISION
 Wichita, Kansas

5-13-54