


15-065-20515-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham County, Sec. 8 Twp. 9S Rge. (E) 21 (W)
Location as "NE/CNWxSWx" or footage from lines SE SW NE
Lease Owner K & E DRILLING, INC.
Lease Name TRAIL Well No. 1
Office Address 816 Union Center - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 12-29 19 71
Application for plugging filed 12-29 19 71
Application for plugging approved 12-29 19 71
Plugging commenced 14:30 P. M. 12-29 19 71
Plugging completed 5:00 P, 12-29 19 71
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nicholes
Producing formation Depth to top Bottom Total Depth of Well 3865 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	208	8 5/8	204	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole @ 950' w/110 CU Ft. 215 w/30 CU Ft. & 40' w/10 CU ft.
2 sx in rat hole

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1972
CONSERVATION DIVISION
Wichita, Kansas

1-4-72

Name of Plugging Contractor B & B Drilling, Inc. (If additional description is necessary, use BACK of this sheet)
Address 720 Union Center - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar
720 Union Center - Wichita, Kansas
(Address)

Subscribed and sworn to before me this 3rd day of January, 19 72

May 31, 1974

Alma A. Neises
Notary Public.

My commission expires

20515
15-065-0000-00-00

(316) 267-0613

B & B DRILLING, INC.

~~207 Petroleum Building~~ 720 UNION CENTER
Wichita, Kansas 67202

December 30, 1971

DRILLERS LOG

Re: Teall #1
SE SW NE Section 8-9S-21W
Graham County, Kansas

OPERATOR: K & E Drilling, Inc.
CONTRACTOR: B & B Drilling, Inc.
COMMENCED: December 20, 1971
COMPLETED: December 29, 1971
TOTAL DEPTH: 3865'

Set 8 5/8" @ 204' w/140 sx.

0	208	Surface
208	540	Shale & Sand
540	1221	Shale & Sand
1221	1799	Sand & Shale
1799	2205	Shale
2205	2280	Shale & Lime
1772	1819	Anhydrite
2280	2503	Shale & Lime
2503	2792	Shale & Lime
2792	3260	Shale & Lime
3260	3325	Lime
3325	3487	Lime
3487	3610	Lime
3610	3825	Lime
3825	3865	Shale & Lime
3865		Total Depth

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1972
CONSERVATION DIVISION
Wichita, Kansas

1-4-72

D & A

We certify the above and foregoing to be true and
Correct copy of the log on the #1 Teall, located
in Graham County, Kansas.

Bill Baker President

Alma A. Neeson Notary Public
Subscribed and sworn to before me this 3rd day
of January, 1972. My commission expires
May 31, 1974.

