


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 8 Twp. 9S Rge. 21W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW NW  
Lease Owner John P. Jennings  
Lease Name Clack #1 = Well No. #1  
Office Address Suite 309, 200 E. 1st, Wichita, Ks. 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 10, 1975 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced April 10, 1975 19  
Plugging completed 19  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor, Palco, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug #1 1000' 70 sx. cement  
Plug #2 200' 20 sx. cement  
Plug #3 40' 10 sx. cement

Completed 3:00 P.M., April 10, 1975

Gilbert Balthazor, State Plugger

RECEIVED  
STATE CORPORATION COMMISSION

APR 10 1975

4-16-75

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor John O. Farmer, Inc.  
Address Box 352, Russell, Kansas 67665

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
John O. Farmer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John O. Farmer  
Box 352, Russell, Kansas 67665  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April, 1975

My commission expires February 15, 1979

HELEN CARLSON Notary Public.

**KANSAS DRILLERS LOG**

15-065-20736-00-00

S. 8 T. 9S R. 21 E W

Loc. SW NW NW  
County Graham

API No. 15 \_\_\_\_\_  
County \_\_\_\_\_ Number \_\_\_\_\_

Operator  
John P. Jennings

Address  
Suite 309, 200 E. 1st, Wichita, Kansas 67202


Well No. #1 Lease Name Clack

Footage Location  
990 feet from (N) XXS line 330 feet from (E) (W) line

Principal Contractor John O. Farmer, Inc. Geologist Don Strong

Spud Date April 2, 1975 Total Depth 3830' P.B.T.D.

Date Completed April 10, 1975 Oil Purchaser D & A



Locate well correctly  
Elev.: Gr. 2268'  
DF 2271' KB 2273'

**CASING RECORD**

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives.
Surface	12 1/4	8-5/8	26	206'	Common	160	3% gel

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used.	Depth interval treated

RECEIVED  
STATE CORPORATION COMMISSION

APR 16 1975

CONSERVATION DIVISION  
Wichita, Kansas

**INITIAL PRODUCTION**

Date of first production \_\_\_\_\_ Producing method (flowing, pumping, gas lift, etc.) \_\_\_\_\_

RATE OF PRODUCTION PER 24 HOURS  
Oil \_\_\_\_\_ bbls. Gas \_\_\_\_\_ MCF Water \_\_\_\_\_ bbls. Gas-oil ratio \_\_\_\_\_ CFPB

Disposition of gas (vented, used on lease or sold) \_\_\_\_\_ Producing interval(s) \_\_\_\_\_

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **John P. Jennings** DESIGNATE TYPE OF COMPLETION: OIL, GAS, DRY HOLE, SWDW, ETC.: **Dry Hole**

Well No. **#1** Lease Name **Clack**

S 8 T 9 S R 21 W

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale & Sand	0	206		
Shale & Shells	206	735		
Sand	735	900		
Shale & Sand	900	1260		
Sand	1260	1500		
Red Bed	1500	1765		
Anhydrite	1765	1798		
Shale & Shells	1798	2294		
Shale & Lime	2294	2430		
Lime & Shale	2430	2875		
Shale	2875	2995		
Shale & Lime	2995	3365		
Lime & Shale	3365	3465		
Lime	3465	3830		
T.D.	3830			
<p>DST #1 1351' to 1365'            Tool Open 45 min.            Rec: 20' mud            FP: 15            BHP: 15</p> <p>DST #2 3820-3830'            Tool Open 30 min.            Rec: 10' mud, spots of oil            FP: 0            BHP: 0</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>John O. Farmer</i>
	Signature
	President/Contractor
	Title
	April 15, 1975
	Date