


15-065-00964-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 9 Twp. 9S Rge. 21 ~~W~~ (W)
Location as "NE/CNW/SW" or footage from lines NE/4 SW/4 NW/4
Lease Owner Barnett Oil Company
Lease Name Eberhardt Well No. 1
Office Address 411 First Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 9, 1957
Application for plugging filed March 11, 1957
Application for plugging approved March 12, 1957
Plugging commenced March 9, 1957
Plugging completed March 9, 1957
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3785 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	194'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 190' with 1/2 sack of hulls on top and 15 sacks of cement; filled with mud to 40'. Set second plug at 40' with 1/2 sack of hulls and wired. Filled hole to bottom of cellar with 10 sacks of cement.


(Well Log Attached)

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnett Drilling, Inc.
Address 409 First Nat'l Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
F. H. Rousey, (employee of owner) ~~operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. H. Rousey
411 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of March, 1957.
My commission expires February 27, 1960.



Millard E. Willis
Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 9 T 9 R21W
BOOK PAGE 147 L 6

MAR 15 1957
3-15-57
CONSERVATION DIVISION

15-065-00964-00-00

BARNETT OIL COMPANY
WELL LOG - EBERHARDT WELL NO. 1
NE/4 SW/4 NW/4 OF SECTION 9-9S-21W
GRAHAM COUNTY, KANSAS

Date started: February 28, 1957
Date completed: March 9, 1957

<u>From</u>	<u>To</u>	<u>Formation</u>
0	35	Surface Clay
35	55	Sand
55	80	Shale and shells
80	100	Sand
100	194	Shale and shells
194	835	Shale
835	1194	Sand and shale
1194	1370	Sand
1370	1685	Shale and shells
1685	1720	Anhydrite
1720	1770	Shale and shells
1770	2200	Shale
2200	2590	Lime
2590	2725	Shale and lime
2725	2865	Shale and shells
2865	3120	Shale and lime
3120	3600	Lime
3600	3624	Lime and shale
3624	3785	Lime (Total Depth) (D.& A.)

Set 194' of new 8 5/8", 24# s.s. casing
with 135 sacks of cement.

PLUGGING	
FILE SEC	9 T 9 R 21W
BOOK PAGE	147 LINE 6

RECEIVED
STATE COMMISSION
3-15-57
MAR 15 1957

CONSERVATION DIVISION
Wichita, Kansas

BARNETT OIL COMPANY

DETACH HERE BEFORE DEPOSITING CHECK. IF THIS VOUCHER IS INCORRECT, RETURN WITHOUT ALTERATION AND EXPLAIN DIFFERENCE.

STATEMENT OF ACCOUNT SETTLED BY THIS VOUCHER

No 20427

Plugging assessment for Eberhardt #1 -
Your File No. 147-6

\$25.00

15-065-00964-00-00

STATE OF KANSAS

15-065-00964-00-00

INVOICE

March 12, 1957

To: Barnett Oil Company
411 First National Bank Building
Wichita, Kansas

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

For: PLUGGING ASSESSMENT AS FOLLOWS:

Eberhardt # 1
NE SW NW 9-9-21W
Graham County
File No. 147-6

\$ 25.00

NOTE: We also need a well log and a well plugging record on this well to complete our file.

Rd. 20427
ck # C-65
3-20-57
E.W.

RETURN THIS COPY WITH REMITTANCE