

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Teton North America LLC
Address: 410 17th Street, Suite 1850, Denver, CO 80202
Phone: (303) 565-4600 Operator License #: 34110
Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4-29-2008 (Date)
by: Ed Schumacher (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-25772-0000
Lease Name: Befort J.B. Enterprises Unit
Well Number: #1 KCCPKTPEL RBPMS
Spot Location (QQQQ): 15th of app. - S/2 - NW -
1980' Feet from North / South Section Line
1335' Feet from East / West Section Line
Sec. 8 Twp. 15 S. R. 17 East West
County: Ellis
Date Well Completed: 4-29-2008
Plugging Commenced: 4:15 PM on 4-29-2008
Plugging Completed: 7:00 PM on 4-29-2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	1122'	8-5/8"	1122'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hole filled with heavy mud. First plug @ 3550' with 25 sxs. Circulated first plug 45 minutes with 55 vis. mud. Second plug @ 1170' with 40 sxs. Third plug @ 460' with 80 sxs. Fourth plug @ 40' with 10 sxs. Plugs displaced with mud. Plugged rat hole with 15 sxs and mousehole with 10 sxs. Total 180 sxs. of 60/40 poz with 4% Gel with 1/4#CF/sx. Allied Cementing plugged well (ticket #33993)

Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 31548
Address: P.O. Box 763, Hays, Kansas 67601

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Teton North America LLC MAY 22 2008

State of Kansas County, Ellis, ss.

CONSERVATION DIVISION
WICHITA, KS

Brian Karlin (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Brian Karlin
(Address) P.O. Box 1378, Hays, Kansas 67601

SUBSCRIBED and SWORN TO before me this 20th day of May

[Signature] My Commission Expires: _____
Notary Public

20 08
NOTARY PUBLIC - State of Kansas
STEVEN THOMASON
My Appl. Expires 9/3/09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]