

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24017-00-00

Spot: W2SWSENE

Sec/Twnshp/Rge: 18-13S-20W

2876 feet from S Section Line, 1251 feet from E Section Line

Lease Name: KOHL - TWIN

Well #: 4

County: ELLIS

Total Vertical Depth: 3950 feet

Operator License No.: 9067

Op Name: DAMAR RESOURCES, INC.

Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3948	0	260 SX
SURF	8.625	1540	0	520SX

128.38

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/13/2008 9:00 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: AVEN WEAVERLING

Company: DAMAR RESOURCES, INC.

Phone: (785) 625-0020

Proposed Plugging Method: Ordered out 550 sxs 60/40 pozmix - 4% gel - 500# hulls.
Wireline fluid level 2950'. PBTB 3900'.
Operator elected to use all cement.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 05/13/2008 11:00 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

LK Wireline perforated two holes at 1520'.
Allied pumped 425 sxs 60/40 pozmix - 4% gel with 500# hulls - circulated cement out 8 5/8".
Shut in 8 5/8" - pumped 60 sxs down 5 1/2" casing.
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3668	3894		
INVOICED			
DATE <u>5-27-08</u>			
INV. NO. <u>2008061764</u>			
RECEIVED			
KANSAS CORPORATION COMMISSION			
MAY 16 2008			

Remarks: ALLIED CEMENTING COMPANY-TICKET #34670.

CONSERVATION DIVISION
WICHITA KS

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

Form CP-2/3

MAY 15 2008