

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21379-00-01
Spot: SENESW Sec/Twnshp/Rge: 33-9S-23W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: RICE ESTATE Well #: 6
County: GRAHAM Total Vertical Depth: 4050 feet

Operator License No.: 5430
Op Name: ENERGY THREE, INC.
Address: 1437 OLD SQ RD STE 201A
JACKSON, MS 39211

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4044	0	w/125 sxs cmt
SURF	8.625	250	0	w/200 sxs cmt

131.63

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 05/14/2008 3:30 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: TIM SCHECK Company: ENERGY THREE, INC. Phone: (785) 483-4096

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel.
Plugged back to 1381'.

Plugging Proposal Received By: DAVID WANN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/14/2008 6:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1300' - pumped 110 sxs 60/40 pozmix - 4% gel to circulate to surface.
Hooked onto backside - pumped 50 sxs 60/40 pozmix - 4% gel.
Pulled all tubing - pumped 10 sxs 60/40 pozmix - 4% gel to top off.

Perfs:

INVOICED
DATE 5-27-08
INV. NO. 2008061766

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 16 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

MAY 15 2008

ENERGY THREE
GORHAM KS 67640

33-09S-23W
SE NE SW

6 RICE ESTATE OWWO

site: 8-1/2 S & 2 W OF HILL CITY KS

cty: GRAHAM

API 15-065-21379

contr: DOC'S WELL SVC

field: LAW WEST

prod: NONE

fr date 02/16/98

spg date 12/06/96

drig comp 12/06/96

card issued 02/16/98

last revised 02/16/98

ELV: 2458 KB, 2453 GL SMP
 tops.....depth/datum
 PBTD1381 + 1077
 ANH2040 + 418
 TOP3521 - 1063
 HEEB3738 - 1280
 TOR3761 - 1303
 LANS3773 - 1315
 MUN CR3890 - 1432
 RTD OLD4050 - 1592
 LOGGED

IP status:
 WSW, CHEY 1312-1332, 01/31/97
 NOTE: CORR 4/21/81 - ORIG FR AS #2 RICE D
 OLD INFO: OPERATOR WAS ENERGY THREE, 6 RICE
 ESTATE, SPD 04/21/81, 04/27/81 8-5/8" 250 / 200 SX, 4-
 1/2" 4044 / 125 SX, OIL, P 15 BOPD, NW, LKC 3927-3931,
 05/21/81 (CARD ISSUED 05/27/82)
 CONTR: BIG THREE DRLG
 DST (1) 3827-3852 (LKC), / 30-45-45-60, REC 290' SLI
 MW, NS ISIP 257# FSIP 257# IFP 29# -79# FFP 99#
 -138#

COPYRIGHT 1998
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

ENERGY THREE
GORHAM KS 67640

33-09S-23W
SE NE SW

6 RICE ESTATE OWWO

1ST (2) 3910-3933 (KC), / 30-45-45-60, 90' GIP, REC 150' TF: 60' HO & GCM (25% OIL), 70' OIL &
 CM (10% OIL), 20' OIL & GCM (10% OIL, 10% W, 80% M), REMARK: HAD CLEAN OIL IN
 DOL ISIP 1076# FSIP 1027# IFP 59# -69# FFP 89# -97#
 1ST (3) 3925-3962 (KC), / 30-45-45-60, 45' GIP, REC 75' OCM (20% OIL), NW ISIP 307# FSIP
 8# IFP 29# -39# FFP 59# -69#
 ICT - CO, PF (MUN CR) 3927-3931, AC 2000 GAL (28% REG), SWB STDY AT 4 BOPH & 0.5
 VPD, POP, IPP 15 BOPD, NW, 5/21/81
 EW INFO: FR 02/16/98, REWORKED 12/06/96 DC 12/06/96 MICT (1/21/97) - CO, PB 1381 TD,
 (CHEY SD) 1312-1332, W / 1 SPF (20 HOLES TOTAL), NO TRTMT, SET 2-3/8" TBG AT 1306,
 D PKR, CONVERTED TO WSW - P 120 BW/24 HRS, 1/31/97