

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21924-00-00
Spot: N2NWNW Sec/Twnshp/Rge: 23-29S-11W
4950 feet from S Section Line, 4620 feet from E Section Line
Lease Name: HISKETT B Well #: 2-23
County: PRATT Total Vertical Depth: 4750 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4465	2440	WITH 250 SX CMT
SURF	8.625	261		WITH 200 SX CMT

154.38

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/12/2008 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND ABCK TO 4600' & 4 SX CMT. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. P;UGA T 270' WITH 50 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/12/2008 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4590' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 15 2008
CONSERVATION DIVISION
WICHITA, KS

Perfs:

Top	Bot	Thru	Comments
2332	2338		

INVOICED
DATE 5-27-08
INV. NO. 2008061767

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 01

RECEIVED
MAY 14 2008
KCC Dodge City

Signed Stephen J Pfeifer
(TECHNICIAN)