

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21404-00-00
Spot: SWNESE Sec/Twnshp/Rge: 10-25S-9W
1639 feet from S Section Line, 1004 feet from E Section Line
Lease Name: SCHMITT Well #: 2-10
County: RENO Total Vertical Depth: 4000 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	8.625	233		
SURF	5.5	3996	2821	<u>130.00</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/06/2008 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: SAND TO 3,800' & TOP WITH 5 SXS CEMENT. RIP 5 1/2" CASING. PULL CASING TO 1,425' & SPOT 35 SXS. CEMENT. PULL CASING TO 825' & SPOT 35 SXS. CEMENT. PULL CASING TO 285' & CIRCULATE CEMENT TO THE SURFACE.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/06/2008 4:30 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

TAGGED SAND @ 3,780' & TOPPED WITH 5 SXS. CEMENT. RIPPED 5 1/2" CASING @ 2,821'. PULLED CASING TO 1,432' & SPOTTED 35 SXS. CEMENT. PULLED CASING TO 823' & SPOTTED 35 SXS. CEMENT. PULLED CASING TO 311' & CIRCULATED 170 SXS. CEMENT TO THE SURFACE. 2/7/2008 - BJ HOPE CHECKED TOP PLUG - CEMENT @ 95' - NOTIFIED OPERATOR TO TOP OFF. PULLED 68 JOINTS OF 5 1/2" CASING.

Perfs:

Top	Bot	Thru	Comments
3848	3878		
INVOICED			
DATE <u>5-27-08</u>			
INV. NO. <u>2008061769</u>			
RECEIVED KANSAS CORPORATION COMMISSION MAY 15 2008 CONSERVATION DIVISION WICHITA, KS			

Remarks: USED 60/40 POSMIX W /4% GEL BY COPELAND ACID & CEMENT. INVOICE #C33439.

Plugged through: CSG

District: 02

Signed Michael R. Wilson
(TECHNICIAN)