

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23447-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 23-16S-26W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: SCHOEPF Well #: 2  
County: NESS Total Vertical Depth: 4640 feet

Operator License No.: 33813  
Op Name: JASON OIL COMPANY, LLC  
Address: 3718- 83RD ST PO BOX 701  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1600		UNKNOWN AMT CMT
PROD	4.5	4638	0	WITH 100 SX CMT
SURF	8.625	389		WITH 225 SX CMT

150-80

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/01/2008 12:20 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JIM SCHOENBERGER Company: JASON OIL COMPANY Phone: (785) 483-4204

Proposed Plugging Method: PLUG AT 3800' WITH 100# HULLS & 25 SX CMT. PLUG AT 1800' WITH 25 SX CMT & 200# HULLS. PLUG AT 1400 CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/01/2008 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMP 100# HULLS & 25 SX CMT AT 3845'. 1ST PLUG AT 1800' WITH 100# HULLS & 25 SX CMT. 2ND PLUG AT 1400' WITH 100# HULLS & 125 SX CMT. LOST CIRCULATION TOWARD END OF LAST PLUG. FLUID DOWN APP. 500'. PUMPED 45 SX CMT DOWN 4 1/2" TO TOP OFF. PUMPED 5 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS.

Perfs:

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 15 2008  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
DATE 5-27-08  
INV. NO. 2008061771

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

RECEIVED  
MAY 12 2008  
KCC Dodge City

Signed Eric MacLaren  
(TECHNICIAN)

*PKT*