

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-20484-00-01  
Spot: SENENE Sec/Twnshp/Rge: 7-34S-2E  
990 feet from N Section Line, 330 feet from E Section Line  
Lease Name: STALNAKER Well #: 1  
County: SUMNER Total Vertical Depth: 3887 feet

Operator License No.: 33763  
Op Name: K-OK GAS COMPANY, LLC  
Address: 8 CRESTVIEW DR PO BOX 1005  
SALINA, KS 67401

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3857		225 SX CMT.
SURF	8.625	200		

126.33

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/21/2008 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2637

Proposed Plugging Method: SAND BACK TO 3060' AND CAPP WITH 4 SKS CMT. RECOVER CASING. CIRC CMT FROM 250-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE  
Date/Time Plugging Completed: 01/21/2008 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3050' AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2301' AND PULLED TO 270' WHERE 85 SKS OF CMT WAS PUMPED. CMT DID NOT CIRC. RAN CSING BACK TO 150' AND PUMPED 52 SKS OF CMT. CMT CIRC TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3551	3556		

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
**MAY 15 2008**  
CONSERVATION DIVISION  
WICHITA, KS

**INVOICED**

DATE 5-27-08  
INV. NO. 2008061772

Remarks: UNITED CMTG 40/60 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

*PLG*