

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-03762-00-00
Spot: NENWSW Sec/Twnshp/Rge: 7-15S-13W
2310 feet from S Section Line, 4290 feet from E Section Line
Lease Name: MAAG Well #: 2
County: RUSSELL Total Vertical Depth: 3328 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3326	0	w/125 sxs cmt
SURF	8.625	448	0	w/unknown sxs cmt

108.16

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/12/2008 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BENNIE DILLS Company: RITCHIE EXPLORATION, INC. Phone: (620) 793-2525

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 1000# hulls.
Perfs - Arb. CIBP at 3300'. Casing parted at 1686'. Well flowing.
Emergency plug with rig over the hole - operator elected all cement plug.
Log Tech perfed at 865' and 498'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/12/2008 8:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Kelso RIH with tubing to 3192'. Allied rigged to tubing - pumped 60 sxs cement with 300# hulls mixed in - followed with 40 sxs 60/40 pozmix - 3% cc and 100# hulls.
Pulled tubing to 1653'. Allied rigged to tubing - pumped 200 sxs 60/40 pozmix with 400# hulls to circulate cement out of 4 1/2" casing.
Pulled tubing - rigged to 4 1/2" casing with a swedge - pumped 25 sxs 60/40 pozmix.
Max. P.S.I. 250#. S.I.P. 200#.
Rigged to 8 5/8" casing - pumped 35 sxs 60/40 pozmix - 4% gel.
Max. P.S.I. 400#. S.I.P. 400#.


Perfs:

INVOICED
DATE 5-27-08
INV. NO. 2008061778

Remarks: ALLIED CEMENTING COMPANY-TICKET #34668.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

CM

Form CP-2/3

MAY 14 2008

PKT

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 16 2008
CONSERVATION DIVISION
WICHITA, KS

151

251181152

DERBY OIL CO. #2 WAAG ³³ Arb 7-15-13W
 NE NW SW 1
 Contr. GLENN W. PEEL DRILLING CO. RUSSELL County
 E 1873 Comm. Comp. 5-20-49 IP 1.61 90PD PHY FOT

Tops	Depth	Datum
LANS	3050	-1177
ARB	3316	-1443
T.O.	3324	-1451

8" 4:7
 5" 3319
 SWB 23 BOFH/3 HRS

+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS