

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-21833-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 18-16S-13W  
1650 feet from S Section Line, 990 feet from W Section Line  
Lease Name: LUERMAN WEEKS Well #: 1  
County: BARTON Total Vertical Depth: 3390 feet

Operator License No.: 6883  
Op Name: ROBINOWITZ OIL COMPANY  
Address: 4200 E SKELLY DR STE 620  
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3389	0	165 SX
SURF	8.625	438	0	280 SX

110.18

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/06/2008 8:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: DON DEGENHARDT Company: ROBINOWITZ OIL COMPANY Phone: (620) 793-2299

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 800# hulls - 13 sxs gel.  
Perf at 1600' - 800' - 425'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/06/2008 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3255'.  
Tied to tubing - pumped 60 sxs 60/40 pozmix - 4% gel with 200# hulls and 13 sxs gel.  
Pulled tubing to 1559' - pumped 100 sxs cement with 150# hulls.  
Pulled tubing to 779' - pumped 110 sxs cement with 200# hulls - circulated to the top.  
Pulled tubing - tied to backside with 20 sxs cement - circulated out casing - shut in.

Perfs:

Top	Bot	Thru	Comments
3374	3376		
3361	3364		

**INVOICED**  
DATE 5-27-08  
INV. NO. 2008061779

RECEIVED  
KANSAS CORPORATION COMMISSION  
**MAY 16 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #33586.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

Form CP-2/3

MAY 07 2008

DRISCOLL LEASE OPERATIONS INC

726 MAIN

#1 LUERMAN & WEEKS

18-16-13W

SE NW SW

RUSSELL, KS 67666

CONTR REVLIN DRILLING INC

CTY BARTON

GEOL \_\_\_\_\_

FIELD TRAPP

E 1930 KB CM 1/31/80 CARD ISSUED 3/27/80 IP P 60 BO & 40 BWPD

ARB 3374-76

+	+
+	+
+	+

API 15-009-21,833

LOG	TOPS	DEPTH	DATUM
SC	888	+1042	
TOP	2805	- 875	
HEEB	3038	-1108	
YOR	3056	-1126	
LKC	3121	-1191	
BKC	3325	-1395	
ARB	3351	-1421	
RTD	3390	-1460	

8-5/8" 441, 5 1/2" 3389

NO DST'S  
MICT - CO, PF (ARB) 3374-76, AC 100,  
SWB LD & REC 18 BFPH, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

7.5.2.0 PF 1.1.1  
20.1.1.1.1

112 112