

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

KCC  
new  
6/16/08

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-135-23243-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued,

Indicate spud or completion date 4/28/1988

WELL OPERATOR: American Energies Corporation KCC LICENSE # 5399  
(owner/company name) (operator's)

ADDRESS: 155 North Market CITY: Wichita

STATE: Kansas ZIP CODE 67202 CONTACT PHONE: 316-263-5785

LEASE: Dugan WELL#: A#2 Section 33 Townshp 16S Range 21W

100' W of W/2 W/2 SE SPOT LOCATION COUNTY: Ness

*Prop. per GPC*  
1347 1320 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)  
2381 2410 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

Check One: Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ D&A \_\_\_\_\_ SWD/ENHR WELL X \_\_\_\_\_ Docket # D25,445

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 268' CEMENTED WITH \_\_\_\_\_ 160 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 4400' CEMENTED WITH \_\_\_\_\_ 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: DV tool set @ 1323' cemented w/250 sx lite Baker AE-1 bridge plug @ 4374'

ELEVATION 2227 G.L. 2232 K.B. T.D. 4430' PBDT \_\_\_\_\_ Anhydrite Depth \_\_\_\_\_

(Stone Corral Formation)

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING:

Junk in hole @ 4374', packer and tubing @ 4374'. Spot 25 sx on top of junk @ 4374' and fill

hole with gel and mud to 1400', cement to surface with 35 sx 60/40 Poz. Hook to annulus

and mix 10 sx 60/40 poz - pressure to 500# - total of 70 sx.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ No (YES,NO) IS ACO-1 FILED? \_\_\_\_\_ Yes (YES,NO)

If not explain why? Currently on file with state

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Thad Starr, American Energies Corporation Phone#: 620-793-2146

Address: 155 N. Market, Suite 710 City: Wichita State: Kansas

PLUGGING CONTRACTOR: Cheyenne Well Service KCC LICENSE #: 6454

(company name) (contractor's)


Address: P.O. Box 384 City: Ness City State: KS Zip 67560

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Mid July, 2008

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY:

Operator  Agent \_\_\_\_\_

DATE: 06/09/08 AUTHORIZED OPERATOR OR AGENT:

  
(signature) Alan L. DeGood, President

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 10 2008

CONSERVATION DIVISION  
WICHITA, KS

# KANSAS

## CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

AMERICAN ENERGIES CORPORATION  
155 N MARKET STE 710  
WICHITA, KS 67202-1821

June 16, 2008

Re: DUGAN #A 2  
API 15-135-23243-00-00  
33-16S-21W, 1347 FSL 2381 FEL  
NESS COUNTY, KANSAS


Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after December 13, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,



Steve Bond

Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888