

KCC
men
6/12/08

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 109-20744-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 5/13/2005

Well Operator: Norstar Petroleum Inc. KCC License #: 31652

Address: 6855 S. Havana St., Suite 250 City: Centennial

State: CO Zip Code: 80112 Contact Phone: (303) 925 - 0696

Lease: Soucie Well #: 1-17 Sec. 17 Twp. 11 S. R. 34 East West

SE SW NE NE Spot Location / QQQQ County: Logan

1240 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

840 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8", 24# Set at: 310' Cemented with: 200 Sacks

Production Casing Size: 4 1/2", 10.5# Set at: 4797' Cemented with: 180 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perf: 4703'-4708', 4668'-4680'. CIBP: 4440'

Perf: 4378'-4380', 4326'-4330', 4292'-4294', 4215'-4218'. CIBP: 4270'.

Elevation: 3238 (G.L. / K.B.) T.D.: 4800 P.B.T.D.: 4270' Anhydrite Depth: 2691

(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): 40 sxs w/ hulls @ 4220',

10 sxs gel spacer w/ hulls (500# hulls), 190 sxs @ 2500' to surf.

25 sxs in annulus if necessary

RECEIVED
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

JUN 12 2008

If not explain why? Submitted with original ACO-1

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dave Pauly

Phone: (316) 250 - 2045

Address: 100 S. Main, Ste 415 City / State: Wichita, KS 67202

Plugging Contractor: Allied Cementing Co. LLC KCC License #: 99996

Address: P.O. Box 31, Russell, KS 67665 Phone: (785) 483-72627

Proposed Date and Hour of Plugging (if known?): 6/16/08

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6/12/08 Authorized Operator / Agent: [Signature] [Signature]

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

NORSTAR PETROLEUM, INC.
6855 S HAVANA ST STE 250
CENTENNIAL, CO 80112-3864

June 17, 2008

Re: SOUCIE #1-17
API 15-109-20744-00-00
17-11S-34W, 1240 FNL 840 FEL
LOGAN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after December 14, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550