

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, Kansas 67202

RECEIVED
FEB 01 1988
FEB 01 1988
CONSERVATION DIVISION
Wichita, Kansas
PLUGGING RECORD
K.A.R.-82-3-117
TYPE OR PRINT
PLACE: Fill out completely
return to Cons. Div.
office within 30 days.

API NUMBER Not Available
LEASE NAME McMillen
WELL NUMBER #3
SPOT LOCATION NE SE SE
SEC. 24 TWP. 8 S RGE. 18 E (W)
COUNTY Rooks
Date Well Completed 2-11-54
Plugging Commenced 1-13-88
Plugging Completed 1-13-88

LEASE OPERATOR The Gene Brown Company
ADDRESS 407 S. Main
Plainville, Kansas 67663

PHONE # 913-434-4811 OPERATORS LICENSE NO. 5635

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas 67601

Is ACO-1 filed? If not, is well log attached? yes

Producing formation Arbuckle & L.K. Depth to top 2906 bottom 3426 T.D. 3426

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Topeka	surface pipe	0		8 5/8	263'	none
	long string	0		5 1/2	3419'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Pumped in 150 sacks of Halliburton light cement, perforated the casing at 1930' in order to get cement to bottom. Cement ordered consisted of 65/35 Pox 10% gel 2% lite w/4# F.C. plus 5 sacks hulls.

Maximum pressure 800# on casing --- 700# on 8 5/8
Approximately 700 ft of 2 1/2 tubing and 3/4 7/8 rods were sanded in and left in the hole. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287
Address Hays, Kansas 67663

STATE OF Kansas COUNTY OF Rooks, ss.

Thomas E. Brown ~~employee of operator~~ or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Thomas E. Brown
(Address) 407 S. Main
Plainville, Kansas 67663

SUBSCRIBED AND SWORN TO before me this 29th day of January, 19 88

Kathy A. Wise
Notary Public

My Commission expires: May 27, 1990