

15-163-03952-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 12-9-53

LEASE NAME Mc MILLAN

WELL NUMBER #1

330 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 24 TWP. 8 RGE. 18 (W)

COUNTY ROOKS

Date Well Completed 12-53

Plugging Commenced 4-21-98

Plugging Completed 4-21-98

RECEIVED
JUL 02 1998
JUL 02 1998

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

CONSERVATION DIVISION
Wichita, Kansas

LEASE OPERATOR THOMAS M. BROWN

ADDRESS Box 250 PLAINVILLE KS 67663

PHONE (913) 434-7141 OPERATORS LICENSE NO. 31824

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on: VERBAL - 4-21-98 (date)

DENNIS HAMEL (KCC District Agent's Name)

ACO-1 filed? YES If not, is well log attached?

Producing Formation ARB-LKC Depth to Top 3152 Bottom 3427 T.D. 3427

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>SURFACE</u>				<u>8 5/8</u>	<u>261</u>	<u>-0-</u>
<u>Production</u>				<u>5 1/2</u>	<u>3423</u>	<u>-0-</u>
<u>TUBING</u>				<u>2 7/8</u>	<u>3420</u>	<u>2600</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was used and the method or methods used in introducing it into the hole. If cement or other plug re used, state the character of same and depth placed, from feet to feet each set
RAW tubing to 2200 - spot 100 SKS CEMENT AND 300 # HULLS - pull to
900 FT - spot 75 SKS CEMENT lost circ - pull to 450 AND CIRC
CEMENT with 25 SKS - pull tubing - AND pump down 5 1/2 with
25 SKS cement At 400 PSI. Shut in At 100 PSI. WELL PLUGGED

Name of Plugging Contractor ALLIED CEMENTING License No. UNKNOWN

Address Box 31 - RUSSELL KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: THOMAS M. BROWN

STATE OF KANSAS COUNTY OF ROOKS, ss.

THOMAS M. BROWN (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.


(Signature) Thomas M Brown

(Address) Box 250 PLAINVILLE KS.

SUBSCRIBED AND SWORN TO before me this 29 day of May, 19 98

Valerie Crawford
Notary Public

My Commission Expires: 1-17-2001



SCHLUMBERGER WELL SURVEYING CORPORATION


HOUSTON, TEXAS



LATEROLOG SURVEY

COUNTY: **ROOKS**
 FIELD of: **ELM CREEK**
 LOCATION: **SEC. 24-8S-18W**
 WELL: **PEARL McMILLEN #1**
 COMPANY: **STANOLIND OIL & GAS CO.**

COMPANY: **STANOLIND OIL & GAS CO.**
 WELL: **PEARL McMILLEN #1**
 FIELD: **ELM CREEK**
 LOCATION: **SEC. 24-8S-18W**
 SW SW SE
 COUNTY: **ROOKS**
 STATE: **KANSAS**

Location of Well:

 LL GR MLL
 Elevation: D.F.: **2007**
 K.B.: **2010**
 or G.L.: **2005**
 FILING No. _____

RUN No.	MLL	LL	
Date	12-20-53		
First Reading	3422	3423.5	
Last Reading	3000	260	
Feet Measured	422	3163.5	
Csg. Schlum.	- - -	260	
Csg. Driller	- - -	260	
Depth Reached	3425	3425	
Bottom Driller	3425	3425	
Depth Datum	KB 5' above GL		
Mud Nat.	Aguage I		
Density	10.3		
Viscosity	39	0	
Resist.	.16 @ 55°F	@ °F	
Res. BHT	.09 @ 104°F	@ °F	
pH	6 @ °F	@ °F	
Wtr. Loss	12 CC 30 min.	CC 30 min.	
Max. Temp. °F	104		
Bit Size	7 7/8		
Opr. Rig Time	3 hrs.		
Truck No.	836-Russe I		
Recorded By	G. D. Rose I		
Witness By	Mr. Hester		

FOLD HERE

APR 11 1954

ROOKS COUNTY, KANSAS