

15-163-01061-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rooks County. Sec. 27 Twp. 8S Rge. (E) 18 (W)

Location as "NE/CNW/SW" or footage from lines SE NW SW  
Lease Owner Chief Drilling Co., Inc.  
Lease Name FLEMING Well No. 1  
Office Address Box 797 - Gt. Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6/20 19 64  
Application for plugging filed 6/20 19 64  
Application for plugging approved 6/20 19 64  
Plugging commenced 6/20 19 64  
Plugging completed 6/20 19 64  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty - Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3460 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	190'	8-5/8"	190'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set @ 550'  
Mixed 20 sacks cement through drill pipe  
1/3 sack hulls and wooden plug set @ 180'  
Mixed 20 sacks cement through drill pipe  
1/3 sack hulls and wooden plug set @ 40'  
Mixed 10 sacks cement through drill pipe

RECEIVED  
STATE CORPORATION COMMISSION

JUN 25 1964


CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Chief Drilling Co., Inc. 625-64  
Address Box 797 - Gt. Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. CHIEF DRILLING CO., INC.

(Signature) V. Richard Hoover  
Box 797 - Gt. Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 1964  
Jan. 26, 1967  
Carmen R. Cook, Notary Public.



15163-01061-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 25 1964  
625-64  
CONSERVATION DIVISION  
Wichita, Kansas

WELL LOG

Chief Drilling Co.,  
Box 797  
Great Bend, Kansas

FLEMING #1  
SE NW SW Sec. 27-8S-18W  
Rooks County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 6/13/64  
Completed: 6/20/64

Casing Record: 8-5/8" @ 190' w/140 sacks GL-3 & 2 sacks Gel.

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Rock	0	80	1984 Gr.
Shale	80	485	1986 D.F.
Sand	485	645	1989 K.B.
Shale & Sand	645	1353	
Anhydrite	1353	1395	
Shale & Shells	1395	1900	
Shale & Lime	1900	2908	
Lime	2908	3120	
Lime & Shale	3120	3162	
Lime	3162	3386	
Lime & Shale	3386	3417	
Conglomerate	3417	3423	
Dolomite	3423	3460	
Total Depth	3460		

<u>FORMATION TOPS</u>	
Anhydrite	1353 + 636
Topeka	2908 - 919
Heebner	3120 - 1131
Toronto	3141 - 1152
Lansing	3162 - 1173
Base Kansas City	3386 - 1397
Conglomerate	3417 - 1428
Arbuckle	3423 - 1434
Total Depth	3460 - 1471

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE NW SW Sec. 27-8S-18W, Rooks County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover  
V. Richard Hoover, President

Subscribed and sworn to before me this 22nd day of June, 1964.

Carmen R. Cook  
Carmen R. Cook, Notary Public



My commission expires: Jan. 26, 1967.