

15-163-20318-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 27 Twp. 8S Rge. (E) 18 (W)

Location as "NE/CNWxSWx" or footage from lines NE SE SE

Lease Owner Abercrombie Drilling, Inc.

Lease Name Kramer Well No. 1

Office Address 801 Union Center, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 1, 1970

Application for plugging filed August 1 (verbally) 1970

Application for plugging approved August 1 (verbally) 1970


Plugging commenced August 1 1970

Plugging completed August 1 1970

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3643 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7 5/8"	233'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 1st plug @ 700' w/50 sx.  
Set 2nd plug @ 210' w/15 sx.  
Set top plug @ 40' w/5 sx.  
Completed 7:00 p.m. 8-1-70.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 6 1970  
CONSERVATION DIVISION  
Wichita, Kansas

8-6-70

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 70

My commission expires November 12, 1973

Sue J. McCoy

Notary Public.

CONTRACTOR'S WELL LOG

15-163-20318-00-00

OPERATOR:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	KRAMER #1
LOCATION:	NE SE SE, Sec. 27-8S-18W Rooks County, Kansas
GEOLOGIST:	Don R. Pate
SPUD DATE:	July 28, 1970
COMPLETION DATE:	August 1, 1970

0	115	Rock & Sand
115	580	Shale
580	690	Sand
690	925	Shale
925	1125	Sand
1125	1419	Shale
1419	1454	Anhydrite
1454	1650	Shale
1650	2280	Shale & Lime
2280	2457	Shale
2457	2762	Lime & Shale
2762	2965	Shale & Lime
2965	3095	Lime & Shale
3095	3200	Lime
3200	3241	Lime & Shale
	3241	Rotary Total Depth

Drilled 237' of 9 5/8" surface hole, and set 7 5/8" surface casing @233' K.B. with 90 sx. cement. Cement circulated. Plug was down at 7:00 p.m. 7-28-70.

<u>ELECTRIC LOG TOPS</u>		<u>ELEVATION</u>
Anhydrite	1414 (+611)	2025 K.B.
B/Anhydrite	1450 (+575)	2023 D.F.
Heebner	3158 (-1133)	2017 G.L.
Toronto	3182 (-1157)	
Lansing	3201 (-1176)	

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 6 1970  
CONSERVATION DIVISION  
Wichita, Kansas

8-6-70

STATE OF KANSAS        )  
                                  ) SS  
COUNTY OF SEDGWICK    )

Jerry A. Langrehr, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KRAMER #1, NE SE SE, Sec. 27-8S-18W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.  
By: Jerry A. Langrehr  
Jerry A. Langrehr  
President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 5th day of August, 1970.

Sue J. McCoy  
Sue J. McCoy, Notary Public

My Commission Expires:  
November 12, 1973