

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-23,213 -00-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Fleming

WELL NUMBER 1

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 27 TWP. 8S RGE. 18 (E) or (W)

COUNTY Rooks

Date Well Completed 1/19/93

Plugging Commenced 1/19/93

Plugging Completed 1/19/93

LEASE OPERATOR Edwin C. Schuett & Sharp Engineering

ADDRESS 1616 Glenarm Place, Suite 1804, Denver, Co 80202

PHONE# (316) -733-5577 OPERATORS LICENSE NO. 30722

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-19-93 (date)

by Marvin Miller (KCC District Agent's Name).

Is ACO-1 filled? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3460'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	236'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 3460'-3427' 40 sks cement @ 285'
 25 sks cement @ 3427' 10 sks cement @ 40'
 25 sks cement @ 1380' 15 sks in rathole
 100 sks cement @ 795' 10 sks in mousehole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506


STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 19th day of January, 1993


 GLENDA R. TIFFIN
 NOTARY PUBLIC
 STATE OF KANSAS
 MY APPT. EXPIRES 2-6-96

Glenda R. Tiffin
 Notary Public
 RECEIVED
 STATE CORPORATION COMMISSION
 JAN 21 1993
 REGISTRATION DIVISION
 WICHITA, KANSAS

Form 67-1
Revised 07-87
1-21-93

15-163-23213-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Edwin C. Schuett & Sharp Engineering
1616 Glenarm Place, Suite 1804
Denver, CO 80202

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Fleming

WELL #1

LOCATION: NE NE SW
Section 27-8S-18W
Rooks County, Kansas

LOGGERS TOTAL DEPTH: 3459'

ROTARY TOTAL DEPTH: 3460'

COMMENCED: 1/13/93

CASING: 8-5/8" @ 236' w/160 sks cement

ELEVATION: 1995' K.B.

COMPLETED: 1/19/93

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Anhydrite	1367'	Lansing-Kansas City	3172'
Shale	1405'	Base Kansas City	3392'
Topeka	2919'	Arbuckle	3427'
Heebner	3912'	R.T.D.	3460'
Toronto	3156'		

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)

Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum

Subscribed and sworn to before me on January 19, 1993.

My commission expires: February 6, 1996.

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1993
CONSERVATION DIVISION
WICHITA, KANSAS

GLENDRA R. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-96


Glendra R. Tiffin, Notary Public