


15-163-00596-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County. Sec. 28 Twp. 8S Rge. 18W (E) (W)
Location as "NE/CNW&SW" or footage from lines. SW SW SW
Lease Owner Lee Phillips Oil Company
Lease Name Thompson Well No. 1
Office Address Union National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-19 19 52
Application for plugging filed 7-19 19 52
Application for plugging approved 7-19 19 52
Plugging commenced 7-19 19 52
Plugging completed 7-19 19 52
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3520 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	228'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Top plug set at 40' with 10 sacks cement
Bottom plug set at 210' with 15 sacks cement

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Anschutz Drilling Company, Inc.
Address 709 Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Leon L. Mehler (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leon L. Mehler
709 Union Nat'l Bk Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of July, 19 52

My commission expires May 2, 1956

24-2675-S 2-52-20M

Notary Public
STATE CORPORATION COMMISSION

JUL 25 1952

CONSERVATION DIVISION
Wichita, Kansas

7-25-52

PLUGGING
FILE SEC 28 T 8 R 18
PAGE 34 LINE 36



DRILLER'S LOG

Lee Phillips Oil Company
 #1 Thompson
 SW SW SW - 28-8S-18W
 Rooks County, Kansas

FROM	TO	
0	180	Shale & chalk rock
180	590	Shale
590	770	Shale & sand
770	1188	Dakota sand
1188	1470	Red bed
1470	1505	Anhydrite
1505	1855	Shale & shells
1855	3215	Lime & shale
3215	3251	K. C. lime
3251	3457	Lime
3457	3475	Lime & shale
3475	3498	Arbuckle lime
3498	3520	Arbuckle
	3520	TOTAL DEPTH
		D&A

COMMENCED: 7-9-52
 COMPLETED: 7-19-52

CASING RECORD

Set 8-5/8" surface casing at 228 feet with 150 sacks cement.

STATE OF KANSAS


COUNTY OF SEDGWICK

I hereby affirm that the foregoing is a true and correct copy of the log of Lee Phillips Oil Company's #1 Thompson, located SW SW SW of Section 28-8S-18W Rooks County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

BY: *Leon L. Mehler*
 Leon L. Mehler

Subscribed and sworn to before me this 22nd day of July, 1952.



Jacqueline Linneman
 Notary Public

My commission expires: May 2, 1956.

28-8S-18W
 31-36

7-25-52
 STATE OF KANSAS
 DEPARTMENT OF REVENUE
 TRANSCRIPTION DIVISION
 WASHINGTON, D.C.