

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Energy Three, Inc.
Address: 211 S. Front Street Russell, Ks. 67665
Phone: () Operator License #: 5430
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-185-12621-00-00
Lease Name: Rose
Well Number: 1
Spot Location (OOQQ): E/2 - NE - SE
2027 Feet from _____ North / South Section Line
309 Feet from East / _____ West Section Line
Sec. 22 Twp. 21 S. R. 12 East West
County: Stafford **KCC PLT P-1 CP2/3**
Date Well Completed: _____
Plugging Commenced: 5-16-08
Plugging Completed: 5-20-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	293'	None
				5-1/2"	3586'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from _____ feet to _____ feet each set.

Pumped 50 sxs. cement on bottom. Perforated casing @700', ran in 700' of tubing, pumped 100 sxs. cement & circulated to surface. Tied onto 5-1/2" casing, pumped 220 sxs. of cement, didn't circulate. Cement fell, ran tubing to 700', pumped 65 sxs. cement, ran in 300' of 1" pipe down backside, pumped 60 sxs. & circulated to surface. Plugging Complete. 60/40 pos, 4% gel.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Energy Three, Inc.
State of Kansas County Rice SS.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

RECEIVED

KANSAS CORPORATION COMMISSION

(Address) P.O. Box 467 Chase, Kansas 67524


JUN 06 2008

SUBSCRIBED and SWORN TO before me this 4th day of June 20 08

CONSERVATION DIVISION
WICHITA, KS

Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKA