

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Keith F. Walker Oil & Gas Company, L.L.C.  
Address: 103 West Boyd Street- Norman, OK 73069  
Phone: (405) 701-0676 Operator License #: 33392  
Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Steve Durrant (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Novinger Depth to Top: 5117 Bottom: 5397 T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: <sup>025</sup> 15-05-20986-00-00  
Lease Name: Dunne  
Well Number: 16#1-16 KCC PRT per CP2/3  
Spot Location (QQQQ): S12-N12 SWNWSE  
1717 Feet from  North /  South Section Line  
2348 Feet from  East /  West Section Line  
Sec. 16 Twp. 34 S. R. 23  East  West  
County: Clark  
Date Well Completed: \_\_\_\_\_  
Plugging Commenced: 05/16/08  
Plugging Completed: 05/20/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	797'	0
				5 1/2"	5600'	1996'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.  
Pumped 40 BBL mud down 5 1/2" casing. Set CIPB @ 5010'. Pumped 10 sx cmt on top. Shot 5 1/2" casing @ 1996'. Laid down same. Pumped 50 sx @ 1200'. Pumped 50 sx @ 820'. Pumped 25 sx @ 270'. Pumped 20 sx @ 40' to surface.

Name of Plugging Contractor: Phil Dollar Oilfield Services, Inc. License #: 33311 RECEIVED KANSAS CORPORATION COMMISSION  
Address: P.O. Box 744 Perryton, TX 79070 JUN 05 2008  
Name of Party Responsible for Plugging Fees: Keith F. Walker Oil & Gas Company, L.L.C. CONSERVATION DIVISION WICHITA, KS  
State of Cleveland County, Oklahoma, ss.  
Sonya King, Engineer Tech of Keith F. Walker Oil & Gas Company, L.L.C. (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) 103 West Boyd Street- Norman, OK 73069



SUBSCRIBED and SWORN TO before me this 2 day of June, 20 08  
Rebecca Casey My Commission Expires: 11-10-09  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten Signature]