

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Mull Drilling Company, Inc.
Address: P.O. Box 2758, Wichita KS, 67201-2758
Phone: (316) 264-6366 Operator License #: 5144
Type of Well: D&A Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4/25/08 (Date)
by: Jack Maclaskey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 135-24768 - 00 - 00
Lease Name: French "A"
Well Number: 1-27
Spot Location (QQQQ): NW - SW - SE - NW
2188 Feet from North / South Section Line
1642 Feet from East / West Section Line
Sec. 27 Twp. 18 S. R. 23 East West
County: Ness
Date Well Completed: 4/29/08
Plugging Commenced: 4/29/08
Plugging Completed: 4/29/08

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	220'	8 5/8"	213'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st plug @ 1560' w/50 sacks. 2nd plug @ 780' w/80 sacks. 3rd plug @ 260' w/50 sacks. 4th plug @ 60' w/20 sacks.
Rathole w/15 sacks. Mousehole w/10 sx. 225 sacks total, 60/40 poz, 4% gel, 1/4# per sack flo-seal.

Name of Plugging Contractor: WW Drilling, LLC License #: 33575
Address: P.O. Box 307, WaKeeney KS 67672
Name of Party Responsible for Plugging Fees: Mull Drilling Company, Inc.
State of Kansas County, Sedgwick, ss.
Mark A. Shreve, President/COO (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 04 2008
CONSERVATION DIVISION
WICHITA, KS



(Signature) _____
(Address) P.O. Box 2758 Wichita KS 67201-2758

SUBSCRIBED and SWORN to before me this 2nd day of June, 20 08
Tannis L. Tritt My Commission Expires: 3.26.2011
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PT

ALLIED CEMENTING CO., INC.

30221

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Ness City
West Bend

DATE <u>10-29-08</u>	SEC <u>27</u>	TWP. <u>18s</u>	RANGE <u>23w</u>	CALLED OUT <u>6:30 AM</u>	ON LOCATION <u>10:30 AM</u>	JOB START <u>2:30 PM</u>	JOB FINISH <u>2:30 PM</u>
LEASE <u>French</u>	WELL # <u>"A"</u>	<u>1-27</u>	LOCATION <u>Ness city 2E 1/4 N 1/4</u>	COUNTY <u>Ness</u>	STATE <u>K.S.</u>		
OLD OR <input checked="" type="checkbox"/> NEW (Circle one)							

CONTRACTOR W-W Rig 2

TYPE OF JOB Rotary Plug

HOLE SIZE 7 7/8 T.D. 4440 ft

CASING SIZE _____ DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE 4 1/2 DEPTH 1560 ft

TOOL _____ DEPTH _____

PRES. MAX 100" MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED 225 # 47 gal

1/4" Flo seal P/A

COMMON	<u>1359x</u>	@	<u>12.30</u>	<u>1,660.50</u>
POZMIX	<u>905x</u>	@	<u>6.85</u>	<u>616.50</u>
GEL	<u>95x</u>	@	<u>18.40</u>	<u>1,65.60</u>
CHLORIDE	_____	@	_____	_____
ASC	_____	@	_____	_____
<u>Flo-seal</u>	<u>51#</u>	@	<u>2.20</u>	<u>112.20</u>
_____	_____	@	_____	_____
_____	_____	@	_____	_____
_____	_____	@	_____	_____
_____	_____	@	_____	_____
_____	_____	@	_____	_____
_____	_____	@	_____	_____
HANDLING	<u>2365x</u>	@	<u>2.10</u>	<u>495.60</u>
MILEAGE	<u>236 X 3 X .09 =</u>			<u>277.00</u>
TOTAL				<u>3,227.40</u>

EQUIPMENT

PUMP TRUCK CEMENTER Mike M.

120 HELPER Tyler W.

BULK TRUCK

342 DRIVER Joe D.

BULK TRUCK

_____ DRIVER _____

REMARKS:

100% Rig was being Down Drilled when got there

2:30 PM Mix 30 ft at 1560 ft

2:30 PM Mix 80 ft at 780 ft

2:30 PM Mix 50 ft at 260 ft

2:30 PM Mix 20 ft at 60 ft

2:30 PM Mix 15 ft at 20 ft

2:30 PM Mix 10 ft at 10 ft

SERVICE

DEPTH OF JOB	<u>1560 ft</u>		
PUMP TRUCK CHARGE			<u>900.00</u>
EXTRA FOOTAGE	_____	@	_____
MILEAGE	<u>3</u>	@	<u>7.00 21.00</u>
MANIFOLD	_____	@	_____
_____	_____	@	_____
_____	_____	@	_____
_____	_____	@	_____
_____	_____	@	_____
TOTAL <u>921.00</u>			

CHARGE TO: Mull Drilling

STREET _____

CITY _____ STATE _____ ZIP _____

Thank you

To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Lonnie Lang

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

Lonnie Lang

PRINTED NAME