

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20692-00-00  
Spot: W2E2W2 Sec/Twnshp/Rge: 18-17S-34W  
2490 feet from S Section Line, 1525 feet from W Section Line  
Lease Name: BARNHART-WILKINSON Well #: 1  
County: SCOTT Total Vertical Depth: 4880 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String Size Depth (ft) Pulled (ft) Comments  
SURF 8.625 223 WITH 160 SX CMT

158.60

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/07/2008 5:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JUAN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 2360' WITH 50 SX CMT. 2ND PLUG AT 1260' WITH 80 SX CMT. 3RD PLUG AT 540' WITH 60 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE  
Date/Time Plugging Completed: 04/07/2008 7:30 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG AT 2360' WITH 50 SX CMT. 2ND PLUG AT 1260' WITH 80 SX CMT. 3RD PLUG AT 540' WITH 60 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:


INVOICED  
DATE 4-23-08  
INV. NO. 2008061600

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 14 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Steve Durrant

(TECHNICIAN)

PVT