

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-21195-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 31-14S-9W  
100 feet from N Section Line, 2475 feet from E Section Line  
Lease Name: SOUKUP B Well #: 1-31  
County: ELLSWORTH Total Vertical Depth: 2890 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	338		225 SX CMT.

93.93

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2006 8:00 AM  
Plug Co. License No.: 33549 Plug Co. Name: LANDMARK DRILLING, LLC  
Proposal Rcvd. from: DICK COLLINS Company: LANDMARK DRILLING LLC Phone: (620) 655-2633

Proposed Plugging Method: PUMP 35 SXS @ 1150', 35 SXS @ 810', PUMP 35 SXS @ 388', PUMP 25 SXS @ 60' TO SURFACE AND PUMP 15 @ RATHOLE.

Plugging Proposal Received By: GREG EVES WitnessType: NONE  
Date/Time Plugging Completed: 12/18/2006 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

PUMPED 35 SXS AT 1150', PULLED DRILL PIPE TO 810' AND PUMPED 35 SXS. PULLED DRILL PIPE TO 388' AND PUMPED 35 SXS. PULLED DRILL PIPE TO 60' AND PUMPED 25 SXS TO CIRCULATE TO SURFACE. PUMPED 15 SXS IN THE RATHOLE.

Perfs:

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 15 2008  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
DATE 4-23-08  
INV. NO 200806601

Remarks: ALLIED CEMENTING TICKET #33486. TOTAL = 145 SXS 60/40 POZ 4% GEL.

Plugged through: DP

District: 02

Signed Greg Eves  
(TECHNICIAN)

Handwritten initials/signature