

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19091-00-01  
Spot: SESWNE Sec/Twnshp/Rge: 31-28S-3E  
2310 feet from N Section Line, 1650 feet from E Section Line  
Lease/Unit Name: RODGERS Well Number: 1  
County: BUTLER Total Vertical Depth: 3300 feet

Operator License No.: 32563  
Op Name: MILLENNIUM OIL & GAS, INC.  
Address: 335 UNICE  
EL DORADO, KS 67042

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 126  
Production: Size feet:  
Liner: Size feet:

8107.25

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/01/2001 2:15 PM

Plug Co. License No.: 30141 Plug Co. Name: SUMMIT DRILLING COMPANY

Proposal Rcvd. from: HAROLD BECK Company: SUMMIT DRILLING COMPANY Phone: (620) 343-3278

Proposed  
Plugging  
Method:

Fill hole with heavy mud and spot cement through the drill pipe. Spot 35 sxs. cement at 250' and spot 25 sxs. cement at 60'.

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 12/01/2001 3:00 PM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Filled hole with heavy mud and spotted cement through the drill pipe. Spotted 35 sxs. cement at 250'. Spotted 25 sxs. cement at 60'.

RECEIVED  
KCC DISTRICT #2

DEC 03 2001

WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY UNITED. INVOICE 3742.

Plugged through: DP

District: 02

Signed Michael R Wilson  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-4-01

INV. NO. 2002061019