

2 030575

3-23-88

API NUMBER 15- 173-20,260-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 35'N
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW SW, SEC. 11, T 26 S, R 2 W/E

365 feet from N/S section line

4290 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3710

Lease Name Erdwien Well # 1

Operator: MIDCO Energy, Inc.

County Sedgwick 103.71

Name & Address 8301 Lakeland Circle

Well Total Depth 3191 feet

Wichita, KS 67207

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Jonathan Oil Company License Number 4231

Address Eldorado, KS 67042

Company to plug at: Hour: 13:00 Day: 21 Month: 3 Year: 19 88

Plugging proposal received from Dick Krehbiel

(company name) MIDCO (phone)

were: Bottom plug 50' above perf dump 4 sxs cement. Shoot and pull casing. Set top plug 50' below surface casing, and cement to surface.

RECEIVED
STATE CORPORATION COMMISSION

APR 4 1988

4-4-88

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Warren Kirkpatrick
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 16:20 Day: 23 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT Ran tools to 2000' could get no further. 2 buckets small gravel

dumped 4 sxs cement by bailer. Pulled 2017' of 4 1/2" casing. Had cement plug and gravel. Ran 2 3/8" tubing to 1710', could get no further. United Cementing #1386

spotted 30 sxs 60/40 pozmix 4% gel. Pulled tubing to 270', pumped 80 sxs 60/40 pozmix 4% gel to surface. Pulled tubing. 3-24-88 Cement fell down hole, Lewis

& West #09417 filled to 2' below surface with redimix (3 yards sand and cement)

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

(Please) observe this plugging.

Signed *Don Thompson*
(TECHNICIAN)

DATE 4-6-88

SEP 13 1988

INV. NO. 20299 3-23 AUG 9 1988