

2030104

API NUMBER 15-173-20, 657-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION N/2 NW/4, SEC. 11, T 26 S, R 2 SE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

330 feet from N/4 section line

1660 feet from W/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5015

Lease Name Grunke Unit Well # 1

Operator: Helland Drly. Co. Inc.
Name & Address: 711 Petroleum Bldg.
Wichita, Ks. 67202

County Sedgwick

Well Total Depth 3370' 109.53 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 220'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Berentz Drly. Co. Inc. License Number 5892

Address Box 428, Eureka, Ks. 67045

Company to plug at: Hour: 11:00 AM Day: 11 Month: 6 Year: 19 84

Plugging proposal received from Kevin Hough

(company name) Berentz Drly. Co. Inc. (phone) 316-267-2845

were: Fill hole/mud, run d.p. to 3300', spot 35 ex. cement, pull d.p. to 1100', spot 35 ex. cement, pull d.p. to 270', spot 35 ex. cement, pull d.p. to sur. push plug 40', spot 15 ex. cement to sur., pump 10 ex. cement in rat hole.

Plugging Proposal Received by Stan Marcotte (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 PM Day: 11 Month: 6 Year: 19 84

ACTUAL PLUGGING REPORT Filled hole/mud, ran d.p. to 3300', spotted 35 ex. cement, pulled d.p. to 1100', spotted 35 ex. cement, pulled d.p. to 270', spotted 35 ex. cement, pulled d.p. to 60', spotted 25 ex. cement, pumped 10 ex. cement in rat hole.

Remarks: Used Berentz Drly. Cementing Unit + Halliburton Bulk truck #163813
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-6-84

INV. NO. 2332

RECEIVED
JUN 20 1984
6-20-84
CONSERVATION DIVISION
WICHITA, KANSAS

Signed Don Thompson (TECHNICIAN)

WL RO