

2 030579

3-25-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 173-20,520-00-00

SE NE, SEC. 11, T 26 S, R 2 XXWE
3460 feet from S section line
790 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3710

Lease Name Eble "B" Well # B-4 ANBCC

Operator: Midco Energy, Inc.

County Sedgwick 95.88

Name & Address P.O. Box 781025

Well Total Depth 2950 PBD 2860 feet

Wichita, KS 67278-1025

Conductor- Pipe: Size 4 1/2" feet 2948

Surface Casing: Size 8 5/8" feet 206

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Jonathan Oil Co., Inc. License Number 4231

Address 804 N. Haverhill Road, Eldorado, KS 67042

Company to plug at: Hour: 16:00 Day: 24 Month: 3 Year: 1988

Plugging proposal received from Lynn Butler

(company name) Jonathan Oil Co., Inc. (phone)

were: Gravel to 50' above top perms, dump 4 sxs cement. Shoot and pull 4 1/2" casing.

Set top plug 50' below surface. Fill with redimix.

Perfs @2875'-2877', 2838'-2840'

Plugging Proposal Received by District #2 Office (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 18:15 Day: 25 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT Small gravel to 2788', dumped 4 sxs cement w/bailer. Shot and pulled 2373' of 4 1/2" casing. Set top bridge from 270'-246'. Lewis & West #09452 dumped 4 1/2 yards (sand and cement) to 3' below surface.

STATE CORPORATION COMMISSION

APR 11 1988

4-11-88

CONSERVATION DIVISION

Remarks: Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED (I did/did not) observe this plugging.

DATE 4-13-88

Signed Don Thompson (TECHNICIAN)

INV. NO. 20365

3-25

AUG 9 1988

SEP 13 1988