

R

CP-3

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1962
7-26-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Raymond Oil Co INC AUB YCC
Complete Address: 410 Union National Bank Bldg Wichita, Ks
Lease Name Mc Mass Well No. 1-B
Location QV 2-S-2NW Sec. 12 Twp. 26 Rge. 2 (E) (W)
County Sedgewick Total Depth 2854
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Southwest Casing Co
Address: Box 364 Great Bend License No. 389
Operation Completed: Hour 12:00 Day 23 Month July Year 1962

The Above well was plugged as follows:

Dump 5 shs cement on Bottom. Pull
Pipe Set Plug @ 200' by 20' Rock bridge +
15 sacks cement, Mud to 30' by 8 shs cement
for cap

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. E. Hess
Well Plugging Supervisor

DATE 7/26/62
INV. NO. 5971-E

R

Francis M. Raymond & Warren Winne
#1 DeMoss "B"
CN/2 S/2 NW/4, 12-26S-2E
(1485' WEL & 330' SNL N/2 S/2 NW/4)
Sedgwick County, Kansas

Contractor: Raymond Oil Co., Inc.

Commenced: 8/25/58
Completed: 8/31/58 (Rotary)

Elevation: 1346 KB

Casing: 8-5/8" @ 168'
5-1/2" @ 2850'

Cement: 150 Sacks
50 Sacks

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Surface Clay	30
Shale & Lime	125
Lime	168
Shale & Lime	500
Lime	830
Lime & Shale	1300
Shale & Shells	1550
Shale & Lime	2146
Lime	2220
Shale & Lime	2396
Lime	2520
Lime & Shale	2745
Shale & Lime	2814
Chert	2820
Dolomite	2825
Lime & Dolomite	2847
Chert	2854

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1962

CONSERVATION DIVISION
Wichita, Kansas

Tops:

Lansing	2146
Kansas City	2359
Base of Kansas City	2526
Mississippi	2814
Mississippi Chat	2847
"Pay Zone"	2850
Rotary Total Depth	2854

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby certify that the above information is true and correct to the best of my knowledge.

Lloyd M. Greenstreet
Lloyd M. Greenstreet

Subscribed and sworn to before me this 5th day of September, 1958.

Betty Baker
Notary Public

My Commission Expires: 2/24/60