

KANSAS

FORM CP-3  
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-173 20 323-00-00

245 North Water  
Wichita, KS 67202

Operator's Full Name Walnut Valley Oil, Inc.

Complete Address 150 S. Rock Rd., Wichita, Ks. 67207

Lease Name DeMoss Well No. # 2

Location E/2 SW. NW. Sec. 12 Twp. 26 Rge. 2 (East) (~~West~~)

County Sedgwick Total Depth 3161'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor H & H Casing Pulling Co.

Address 8 East 3rd. Hutchinson, Ks. 67501 License No.     

Operation Completed: Hour: 3:00 PM Day: 26 Month: 3 Year: 1981

The above well was plugged as follows:

8 5/8" sur. csg. 220' circ./cent. 4 1/2" csg. 3160'

Sand hole to 3150', dumped 4 sx. cent.

Shot & pulled 2000' 4 1/2" csg. Left 1160' csg. in hole.

Set top bridge (rock) 230'.

Dumped 4 yds. redi-mix to 4' below ~~xxxx~~ ~~xxxx~~ ground level.

RECEIVED  
STATE CO. IN COMMISSION  
3-31-81  
MAR 31 1981

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 4-6-81

INV. NO. 8861-E

Signed: Don Thompson  
Conservation Division Agent