

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Call me at 10/1/08

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 185-10481-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date Spud 1/17/1961

Well Operator: Chesapeake Operating, Inc. KCC License #: 32334
(Owner / Company Name) (Operator's)

Address: P.O. Box 18496 City: Oklahoma City

State: Oklahoma Zip Code: 73154-0496 Contact Phone: (405) 879 - 9375

Lease: Nagel Well #: B-1 Sec. 3 Twp. 24 S. R. 15 East West

SE SE SW Spot Location / QQQQ County: Stafford

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2970 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 252' Cemented with: 185 Sacks

Production Casing Size: 5 1/2" Set at: 4,124' Cemented with: 650 Sacks

List (ALL) Perforations and Bridgeplug Sets: Lansing/Kansas City (3,710' - 3,820'), Mississippi (3,984' - 4,020')

Elevation: 2,023' (G.L. / K.B.) T.D.: 4,120' PBDT: 4,100' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Set CIBP at 3,700' w/ 10 sacks of cement. Circulate cement from casing leak at 842' to surface if possible, if not set 25 sack cement plug from 725'. Load hole with 9.0 ppg plugging mud. Top off with 25 sacks of cement.

Tie onto 5 1/2" x 8 5/8" annulus and pump 50 sacks down backside. Cut off WH, weld on cap, and clean up surface location.

**RECEIVED
KANSAS CORPORATION COMMISSION**

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

JUN 03 2008

If not explain why? _____

**CONSERVATION DIVISION
WICHITA, KS**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Bud Neff, Production Superintendent Phone: (620) 277 - 0803 ext. 11

Address: 4532 W. Jones Avenue City / State: Garden City, KS 67846

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 9996
(Company Name) (Contractor's)

Address: P.O. Box 31, Russell, KS 67665 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): (612 N. CLAY AVE., MEDICINE LODGE, KS 67014)

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6/2/08 Authorized Operator / Agent: Doug Heweth by Aloha Dewbre-King
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



Aletha M. Dewbre-King
Regulatory Compliance Specialist

June 2, 2008

VIA UNITED PARCEL SERVICE

Kansas Corporation Commission
Conservation Division
Finney State Office Building
130 South Market, Room 2078
Wichita, Kansas 67202

Re: Nagel B-1
3-24S-15W
Stafford Co., KS
API #15-185-10481

Dear Sir or Madam:

Enclosed is a CP-1 form for the referenced well.

If additional information is required, please contact me at the telephone number or e-mail address below or Doug Howeth at (405) 879-9375.

Sincerely,

Chesapeake Operating, Inc.

A handwritten signature in cursive script that reads "Aletha M. Dewbre-King".

Aletha M. Dewbre-King

Enclosures

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 03 2008

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

CHESAPEAKE OPERATING, INC.
6200 N WESTERN AVE
PO BOX 18496
OKLAHOMA CITY, OK 73118-1046

June 09, 2008

Re: NAGEL B #1
API 15-185-10481-00-00
3-24S-15W, 330 FSL 2970 FEL
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after December 6, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888