

WELL PLUGGING RECORD

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
-Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Sedgwick County, Sec. 16 Twp. 26S Rge. 2E (E) XXXX

Location as "NE/CNW&SW&" or footage from lines NE NW SE

Lease Owner Spencer Drilling Company

Lease Name Lygrisse Well No. 1

Office Address Box 570, Lyons, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-25, 19 61

Application for plugging filed 4-25, 19 61

Application for plugging approved 4-25, 19 61


Plugging commenced 4-25, 19 61

Plugging completed 4-25, 19 61

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Lee Guthrie

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3411' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 1/2"	140'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy Rotary Mud to 180' - set plug and cemented with 25 sacks of cement. Filled with heavy Rotary Mud to 30' - set plug and cemented with 10 sacks of cement. 2 1/2 sacks of cement in Rat Hole

RECEIVED  
STATE CORPORATION COMMISSION  
4-28-61  
APR 28 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Drilling Company, Inc.

Address P. O. Box 786, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss. O. N. Wilson (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

RED DRILLING COMPANY, INC.

(Signature) O. N. Wilson O. N. Wilson

Box 786, El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 27th day of April, 19 61

My commission expires April 9, 1963

Edith S. Liggett  
Edith S. Liggett Notary Public.



# WELL LOG

Operator Spencer Drilling Company  
 Comm 4-6-61 Comp 4-25-61  
 Shot \_\_\_\_\_ Qts. From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
 Acidized \_\_\_\_\_ Gal. \_\_\_\_\_  
 Prod. Formation \_\_\_\_\_  
 Initial Prod. Dry Hole  
 Elevation \_\_\_\_\_ Cemented

Lease Lygrisse Well No. 1  
 Loc NE NW SE Sec 16 Twp 26S Rge 2E  
 County Sedgwick State Kansas  
 Contractor Red Drilling Company, Inc.

### Casing Record

Size	Ft.	Pulled	Remarks
10 1/2"	140'	W/170 Sacks	4 Sks. C.C.
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

### FIGURES INDICATE BOTTOM OF FORMATION

3	Cellar
40	shale & gravel
100	lime & shale
140	lime & shale strks
250	lime & shale brks
470	lime
630	shale & lime
690	lime
780	shale & lime
1820	shale & lime strks
1935	lime & shale brks
2115	shale
2180	lime & shale
2210	shale & lime strks
2260	shale
2388	lime & shale
2461	shale & lime shls
2470	lime & shale
2579	lime
2637	lime - chalky lime
2940	lime & shale
3017	lime & Chert
3086	Cherty lime
3197	lime
3205	lime & shale
3250	shale
3297	lime
3317	sand
3336	sand & shale
3347	sand
3384	sand & shale
3411	lime

Total Depth 3411'

This is to certify the above log is true and correct.

RED DRILLING COMPANY, INC.

BY O. N. Wilson  
O. N. Wilson

Subscribed and sworn to before me this 27th day of April, 1961

My commission expires

April 9, 1963

Edith L. Riccett  
Notary Public

