

STATE OF KANSAS  
STATE CORPORATION COMMISSION

## WELL PLUGGING RECORD

**OR**

**Strike out upper line when reporting plugging off formations.**

## FORMATION PLUGGING RECORD

**Give All Information Completely**  
**Make Required Affidavit**  
**Mail or Deliver Report to:**  
**Conservation Division**  
**State Corporation Commission**  
**800 Bitting Building**  
**Wichita, Kansas**

NORTH


**Locate well correctly on above  
Section Plat**

Sedgwick County. Sec. 16 Twp. 26S Rge. 2 (E) E (W)

Location as "NE $\frac{1}{4}$  NW $\frac{1}{4}$  SW $\frac{1}{4}$ " or footage from lines. NE $\frac{1}{4}$  NW $\frac{1}{4}$  NW $\frac{1}{4}$

Lease Owner. THRIFTY DRILLING, INC.

Lease Name. Bowlin Well No. 1

Office Address. 600 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole). Dry hole

Date well completed. November 23 1948

Application for plugging filed. January 15 1949

Application for plugging approved. January 17 1949

Plugging commenced. February 6 1949

Plugging completed. February 6 1949

Reason for abandonment of well or producing formation. Dry hole

If a producing well is abandoned, date of last production.....19.....  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced?.....**Yes**.....

Name of Conservation Agent who supervised plugging of this well..... D. C. Lilley

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 2927 Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

### CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to .....feet for each plug set.

Fresh water plug mudded to surface  
5 sacks of cement at 2924'

Mud to 95'

10 sacks of cement on a 10' rock bridge

Mud to surface

5 sacks of cement as top cap

(If additional description is necessary, use **BACK** of this sheet)

Correspondence regarding this well should be addressed to THRIFTY DRILLING, INC. Box 545  
Address 600 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick

Anetia Buffington

..(employee of owner) or ~~(owner or operator)~~ of the above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. **THRIFTY DRILLING, INC.**

THRIFTY DRILLING, INC.

By: Archie Buffington  
(Signature) Asst. Secretary  
600 Petroleum Building, Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this.


day of

.., 1949

My commission expires.

My commission expires Feb. 26, 1951.

Notary Public.



## WELL LOG

Company:	THRIFTY DRILLING, INC.	Elevation:	1381'
Farm:	Bowlin, well #1	Commenced:	October 16, 1948
Total Depth:	2927'	Completed:	November 23, 1948
Casing Record:	42' of 8 5/8" surface casing cemented with 42 sks. 2916' of 4 1/2" prod. casing. Pulled 2689.2' of 4 1/2".	Plugged:	February 6, 1948
		Description:	NE/4 NW/4 NW/4 Section 16, Township 26 South, Range 2 East, Sedgwick County, Kansas

(Figures indicate bottom of formations)

Shale and Lime Shells	70'
Shale and Lime	335
Lime	500
Shale	595
Red Bed	610
Shale and Lime	655
Lime	685
Shale and Lime	710
Lime and Sandy Lime	760
Shale and Lime	770
Lime	800
Shale and Shells	1475
Shale and Lime	1545
Lime	1710
Shale and Lime	2350
Shale and Shells	2477
Kansas City Lime	2645
Shale and Lime	2700
Lime	2725
Shale and Lime	2840
Shale and Lime Shells	2855
Shale	2909
Variegated Shale	2917
Mississippi Lime	2919
Rotary Total Depth	2920
Mississippi Lime	2927
Total Depth	2927'

RECEIVED

C. S. D. D. D.

APR - 5 1949

S. S. CORPORATION  
COMMISSION  
KANSAS