


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sedgwick County, Sec. 13 Twp. 26 Rge. 2 (E) (W)
Location as "NE/CNW%SW%" or footage from lines NW-SE-SE
Lease Owner John P. Gaty
Lease Name Wheeler Well No. 1
Office Address 11 Cypress Dr., Wichita 6, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 22, 19 60
Application for plugging filed November 2, 19 60
Application for plugging approved November 3, 19 60
Plugging commenced November 3, 19 60
Plugging completed November 5, 19 60
Reason for abandonment of well or producing formation Oil depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production October 26, 19 60
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lee N. Guthrie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3194 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rock and 5 sacks cement from 3194' to 3180'
Mud to 200'
20' Rock bridge and 25 sacks cement at 200'

Mud to 25'

5' Rock bridge cement to surface.


RECEIVED
STATE CORPORATION COMMISSION
12-13-60
DEC 13 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor John P. Gaty
Address 11 Cypress Drive, Wichita 6, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Earl Wentworth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl Wentworth
734 Pippin Court, Wichita, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 1st day of December, 19 60

J. Arnold Dowd
Notary Public.

FORMATION LOG

R

WHELLER #1
 NW-SE-Se
 Sec. 13-26-2E
 Sedgwick County, Kansas
 OPERATOR: JOHN P. GATY

Commenced March 5, 1960

3196.60 ft. or 105 joints
 of 7" O.D. casing cemented
 with 50 sacks of regular by
 Halliburton, March 14, 1960.

Packer set 2 ft. up from
 bottom. Bottom joint 29.50 ft.

	<u>Ft.</u>	<u>Ft.</u>
Shale	0	80
Lime & shale	80	715
Shale	715	1140
Shale & lime	1140	1500
Lime & shale	1500	2280
Shale & lime	2280	2455
K. C. Lime	2455	2570
Shale & lime	2570	2844
Mississippi lime	2844	2920
Lime & chert	2920	3025
Lime & shale	3025	3052
Lime	3052	3145
Lime & shale	3145	3180
Shale & sand	3180	3191
Hunton Lime	3191	3194
Total Depth	3194	

I certify this to be a true and exact copy of formation, taken from
 the Daily Drilling Reports.

Harold Martin Drilling Co., Inc.

Signed: Harold U. Martin
 Harold U. Martin President

Sworn to before me this 18th day of March 1960.

My Commission Expires October 13, 1962

Signed: Dorothy Ellen Martin
 Notary Public

COPY

RECEIVED
 STATE CORPORATION COMMISSION

DEC 13 1960

CONSERVATION DIVISION