


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Sedgwick County, Sec. 13 Twp. 26 Rge. 2 (E) E (W)  
Location as "NE/CNW/SW" or footage from lines SW NE NW  
Lease Owner Frank J. Black  
Lease Name Stollei "A" Well No. 2 SWD  
Office Address McPherson, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Disposal Well  
Date well completed 10-11-57 19\_\_\_\_  
Application for plugging filed 11-16-62 19\_\_\_\_  
Application for plugging approved 11-19-62 19\_\_\_\_  
Plugging commenced 11-20-62 19\_\_\_\_  
Plugging completed 11-23-62 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4082 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 115'   | None       |
|           |         |      |    | 5-1/2" | 3503'  | 2911'      |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, pushed plug to 3400' and dumped 5 sacks of cement with dump bailer. Pulled 5 1/2" casing, bailed hole to 150', set rock bridge and ran 20 sacks of cement. Mudded to 30', set rock bridge and ran 8 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 10 1962

12-10-62

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 62

May 20, 1964

Milton J. Volin  
Notary Public.

My commission expires \_\_\_\_\_



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

copy


Company- BEDELL-CATT DRIG. CO.  
Farm- Stollei "A" No. 2

SEC. 13 T. 26 R2E  
SW NE NW

Total Depth. 4082'  
Comm. 10-2-57  
Shot or Treated.  
Contractor. Winne Oil Co.  
Issued. 4-19-58

DEEPENING RECORD  
Comp. 10-11-57

County Sedgwick  
KANSAS



Elevation. 1394' KB

Production. SWDW

Figures indicate Bottom of Formations.

|                  |      |
|------------------|------|
| surface hole     | 115  |
| shells, shale    | 425  |
| lime             | 970  |
| shale, shells    | 1655 |
| shale, lime      | 1790 |
| lime             | 1920 |
| shale, shells    | 2105 |
| lime, shale      | 2200 |
| lime             | 2285 |
| lime, shale      | 2380 |
| Kansas City lime | 2555 |
| lime             | 2660 |
| lime, shale      | 2850 |
| shale, shells    | 2900 |
| lime, shale      | 2917 |
| Mississippi lime | 2950 |
| Total Depth      |      |

|               |      |
|---------------|------|
| TOPS: Scout   |      |
| Lansing       | 2202 |
| Kansas City   | 2416 |
| B/Kansas City | 2582 |
| Marmaton      | 2648 |
| Mississippi   | 2874 |
| Chat          | 2912 |

DEEPENING RECORD:

Production: SWDW  
T.D. -4082'  
Comm. -10-4-57  
Comp. -10-18-57  
Total Depth 4082'

|              |      |
|--------------|------|
| Tops: Scout  |      |
| Kinderhook   | 3163 |
| Viola        | 3210 |
| Simpson      | 3259 |
| Arbuckle     | 3351 |
| Granite Wash | 4055 |
| Granite      | 4077 |
| Greenwich    | 4082 |

RECEIVED  
STATE CORPORATION CO.

DEC 10 1962

CONSERVATION DIVISION  
Wichita, Kansas