

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY SEDGWICK SEC. 17 TWP. 26S RGE. 2E E/W  
Location as in quarters or footage from lines:  
135' fnl 260' fwl nw/4


Lease Owner WILEY R. ASH JR.  
Lease Name GALYARDT Well No. 3  
Office Address 260 N. ROCK RD. WICHITA, KS. 67206  
Character of Well (Completed as Oil, Gas or Dry Hole): OIL  
Date Well Completed 10- 21- 79  
Application for plugging filed 7-13-82  
Plugging commenced 7-19-82  
Plugging completed 7-21-82  
Reason for abandonment of well or producing formation DRY HOLE

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DON THOMPSON  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3440

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				4 1/2"		2773.95

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

SET PLUG AT 3300 with 4SACKS OF CEMENT WITH 15' ROCK BRIDGE.  
MUDDERED HOLE TO 320' MADE 15' ROCK BRIDGE AND FILLED WITH 4YARDS OF READY MIX.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor H & H CASING PULLING CO.  
BOX 563 BURRTON, KS. 67020

~~STATE OF KANSAS~~ COUNTY OF HARVEY, ss. \_\_\_\_\_

DONALD H. HURST (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Donald H. Hurst  
Box 563 Burrton, Ks. 67020  
(Address)

SUBSCRIBED AND SWORN to this 22 day of July, 19 82



My Commission expires: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public

JUL 23 1982  
7-23-82  
CONSERVATION DIVISION  
Wichita, Kansas



# L. A. KNEBLER CONCRETE & SUPPLY

P. O. Box 340  
Augusta, Kansas 67010

Andover  
733-1395  
16063 E. 13th

Augusta  
775-2211  
714 Ohio

CUSTOMERS  
ORDER NO. \_\_\_\_\_

DATE: 7-21 19 82

NAME \_\_\_\_\_

ADDRESS \_\_\_\_\_

DRIVER	TRUCK	TIME LOADED	CHARGE	C.O.D.	
KR	9	5:00	10:00		
CU. YDS.	LBS.	DESCRIPTION		UNIT PRICE	AMOUNT
5		CONCRETE 3000 Sand mix			
		SAND			
		ROCK			
		CEMENT			
		CALCIUM CHLORIDE			
		COLOR			
		REBAR			
		EXPANSION JOINT			
		WIRE MESH			
		DRIVER NOTE:			
	20	WATER ADDED			
		HOLDING TIME			
		MILEAGE			
		DELIVERY			
<p>TERMS: NET 10th. AFTER 30 DAYS A SERVICE CHARGE OF 2% PER MONTH - 24% ANNUAL RATE WILL BE CHARGED ON PAST DUE ACCOUNTS.</p>					
<p><b>RECEIPT AND RELEASE</b></p> <p>IN CONSIDERATION OF YOUR MAKING DELIVERY ACROSS THE STREET CURB, AT OUR REQUEST WE AGREE TO BE RESPONSIBLE FOR ALL DAMAGES DONE TO SIDEWALKS, DRIVEWAYS, BUILDINGS, GROUNDS OR OTHERWISE.</p> <p style="text-align: center;">RECEIVED THE ABOVE MATERIAL IN GOOD CONDITION.</p>				<p>MDSE. TOTAL</p>	
<p><b>D 2799</b></p> <p style="text-align: right;">SIGNED: <i>Do Furst</i></p>				<p>SALES TAX</p>	
				<p>TOTAL</p>	

**RECEIVED**  
 STATE CORPORATION COMMISSION  
**JUL 26 1982**  
 CONSERVATION DIVISION  
 Wichita, Kansas

LV. PLANT	LV. JOB <u>3:10</u>
AR. JOB <u>2:30</u>	AR. PLANT

# L. E. CARTER

Petroleum Geologist

307 INS. BLDG. 267-2489 WICHITA, KANSAS 67202

2489  
XXXXXX

## GEOLOGIST'S REPORT

### DRILLING TIME AND SAMPLE LOG

COMPANY <u>Wiley R. Ash, Jr.</u>	ELEVATIONS
LEASE <u>Galyardt No. 3</u>	K.B. <u>1425</u>
FIELD <u>Fairview</u>	D.F. <u>1423</u>
Approx. NW NW NW/4	G.L. <u>1420</u>
LOCATION <u>135' ENL &amp; 260' FWL NW/4</u>	Measurements-Are All
SEC: <u>17</u> TWSP: <u>26S</u> RNG: <u>2E</u>	From <u>K.B. 1425</u>
COUNTY <u>Sedgwick</u> STATE <u>Kansas</u>	
CONTRACTOR <u>Blue Streak Drlg. Co.</u>	CASING
SPUD <u>10-10-79</u> COMP. <u>10-21-79</u>	SURFACE <u>8 5/8" @ 211'</u>
RTD <u>3437'</u> LTD <u>3440'</u>	PRODUCTION <u>1/2" @ 3440'</u>
Chem-Gel <u>2950'</u> Fresh Chem.	ELECTRICAL SURVEYS
MUD UP <u>Gel 785'</u> TYPE MUD <u>Gel</u>	Petro-Log
	Radiation Guard L-3

### FORMATION TOPS & STRUCTURAL POSITION


FORMATION	DRILLING TIME	ELECTRIC LOG TOP	SUB-SEA DATUM	STRUCTURAL POSITION		
				A	B	C
KC Drum Lm	2524	2526	-1101	-1108	-1103	-1098
Base Kansas City	2693	2695	-1270	-1277	-1273	-1265
Marmaton Lm	2754	2758	-1333	-1339	-1333	-1330
Cherokee Sh	2944	2946	-1521	-1526	-1521	-1517
Top Mississippian	2985	2987	-1562	-1570	-1570	-1572
KHK-Boice SH	3260	3264	-1839	-1844	-1840	-1830
Chattanooga SH	3293	3298	-1873	-1891	-1884	-1874
Hunton Dolm	3325	3330	-1905	-1913	-1906	-1899
Maquoketa Sh	3342	3348	-1923	-1924	-1923	-1907
Viola Dolm	3346	3352	-1927	-1929	-1926	-1915
Simp. Platteville Dolm	3366	3369	-1944	-1950	-1946	-1936
Simp. Glenwood Sd	3376	3379	-1954	-1960	-1956	-1946
Simp. St. Peter Sh	3410	3413	-1988	-1991	-1988	-1978
Simp. St. Peter Sd	3417	3420	-1995	-1999	-1996	-1985

#### REFERENCE WELLS FOR STRUCTURE

Electric Log Data

- A. DNB Drlg. Co. Sample "A" #1, NE NE NE/4 18-26S-2E
- B. Wiley R. Ash, Jr. Galyard #1, NW NW NW/4 17-26-2E
- C. Wiley R. Ash, Jr. Tjaden "B" #2, SW SW SW/4 8-26S-2E

The Depth Quantities For Each Rock Unit Are Indicated  
 A - No Spans Indicated  
 B - By Run For 100 WLT  
 C - By Run For 50 Fm.



RECEIVED  
STATE CORPORATION COMMISSION

JUL 14 1982

CONSERVATION DIVISION  
Wichita, Kansas