

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY SEDGWICK SEC. 17 TWP. 26S RGE. 2E E/W
Location as in quarters or footage from lines:
NE NW NW 320' FNL & 1,100' FWL NW NW/4

Lease Owner WILEY ASH JR.
Lease Name GALYARDT Well No. 7
Office Address 260 N. ROCK RD. WICHITA, KS. 67206
Character of Well (Completed as Oil, Gas or Dry Hole): OIL
Date Well Completed 9-23-81
Application for plugging filed 7-13-82
Plugging commenced 7-16-82
Plugging completed 7-19-82
Reason for abandonment of well or producing formation DRY

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DON THOMPSON

Producing formation _____ Depth to top _____ bottom T.D. 3500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				4 1/2		2513.73'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

SET PLUG AT 2975' - 4 SX CEMENT - 15' ROCK BRIDGE
UNITED FILLED WITH 110 SX COMMON CEMENT - 3 SX HUEL.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H & H CASING PULLING CO.
BOX 563 BURRTON, KS. 67020


STATE OF KANSAS COUNTY OF RENO, SS.

DONALD H. HURST (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Donald H. Hurst
2900 acres Rd. Hutchinson
(Address) Ks.

SUBSCRIBED AND SWORN TO before me this

21st day of July, 19 82



My Commission expires: _____

RECEIVED, 19 82
STATE CORPORATION COMMISSION
Madeline Hurst
Notary Public.
JUL 23 1982
7-23-82
CONSERVATION DIVISION
Wichita, Kansas

L. E. CARTER

Petroleum Geologist

301 WEST CENTRAL

P.O. BOX 2074

WICHITA, KANSAS 67201

OFFICE PHONE
(316) 267-2489

HOME PHONE
(316) 723-7241

GEOLOGIST'S REPORT

DRILLING TIME AND SAMPLE LOG

COMPANY <u>WILEY R. ASH, JR.</u>	ELEVATIONS
LEASE <u>Galyardt - Well No. 7</u>	K.B. <u>1434'</u>
FIELD <u>Fairview</u>	D.F. <u>1431'</u>
LOCATION <u>320' FNL & 1,100' FWL NW NW/4</u>	G.L. <u>1429'</u>
SEC. <u>17</u> TWSP. <u>26-S</u> RNG. <u>2-E</u>	Measurements Are All
COUNTY <u>Sedgwick</u> STATE <u>Kansas</u>	From <u>1434' K.B.</u>
CONTRACTOR <u>Triangle Drlg. Co., Inc; Rig #1</u>	CASING
SPUD <u>9-10-81</u> COMP. <u>9-23-81</u>	SURFACE <u>8 5/8 @ 257'</u>
RTD <u>3,500 Ft.</u> LTD <u>3,505 Ft.</u>	PRODUCTION <u>4 1/2" @ 3504'</u>
<u>Fresh Gel: 2766'</u> <u>Chemical-Fresh</u>	ELECTRICAL SURVEYS:
MUD UP <u>Chemical: 2983'</u> TYPE MUD <u>Gel.</u>	<u>Petro-Log's Radiation -</u>
	<u>Guard & S.P. -Ind. Log</u>

FORMATION TOPS & STRUCTURAL POSITION

FORMATION	DRILLING TIME	ELECTRIC LOG TOP	SUB-SEA DATUM	STRUCTURAL POSITION		
				A	B	C
Kansas City - Drum Lm	2536	2541	-1107	-1099	-1117	-1102
Base Kansas City	2701	2705	-1271	-1269	-1288	-1280
Marmaton Lm	2765	2768	-1334	-1332	-1352	-1345
Cherokee Sh	2754	2957	-1523	-1521	-1542	-1540
Burgess Sand	2994	2997	-1563	-1554	-1584	-1578
Top Mississippian	2999	3002	-1568	-1566	-1597	-1589
Kinderhookian Sh	3279	3282	-1848	-1856	-1859	-1874
Hunton Dolm	3344	3346	-1912	-1924	-1924	-1941
Viola Dolm	3368	3370	-1936	-1940	-1944	-1958
Simp.-Platterville Dolm	3384	3386	-1952	-1960	-1964	-1980
Simp.-Glenwood Sd.	3395	3397	-1963	-1971	-1975	-1990
Simp.-St. Peter Sh	3424	3426	-1992	-1998	-2007	-2022
Simp. St. Peter Sd	3435	3437	-2003	-2012	-2015	-2030
Arbuckle Dolm	3479	3473	-2048	Not	Not	-2075

REFERENCE WELLS FOR STRUCTURE Drilled Drilled
Electric Log Subsea Data

- A. Wiley R. Ash, Jr. - Tjaden "B" - #7, C S/2 SW/4 8-T26S-R2E
- B. Wiley R. Ash, Jr. - Tjaden "B" - #3, SE SW SW/4 8-T26S-R2E
- C. Wiley R. Ash, Jr. - Tjaden "B" - #1, C NE SW/4 8-T26S-R2E

RECEIVED
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1982

JUL 14 1982

CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION
Wichita, Kansas