

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER Drilled 1943 15-019-19491-00-00  
SWSWSW Sec/Twp/Rge 32-33S-12E  
643 feet from south section line  
5049 feet from east section line 35.00

TECHNICIAN'S PLUGGING REPORT OK KCC PRT  
Operator License # 5970  
Operator: JOHN ELMORE  
Name & 776 HIGHWAY 99  
Address SEDAN KS 67361

Lease/Well# ALFORD 2  
County CQ  
Well Total Depth 1142 feet  
Production Pipe: 6.625 Size Feet 898  
Surface Casing:          Size Feet         

AB oil well XXX Gas Well          SWD Well/ Input Well          D & A           
Other well as hereinafter indicated:         

Plugging Contractor: ELMORE'S INC. Lic. # 32884  
Address: P.O. BOX 87 SEDAN KS 67361

Company to plug at: Hour: 3:00P.M. Day: 23 Month: 11 2007

Plugging proposal received from: JOHN ELMORE

Company Name: ELMORE'S INC. Phone: 620-725-5538

Were: GEL HOLE, 25 SX @ TD, 20 SX AT 700', 350' TO SURFACE.

Plugging Proposal Received by: MIKE HEFFERN

Plugging attended by Agent: All          Part                   None XXX  
TECHNICIAN

Operations Completed: Hour:          Day: 26 Month: 11 2007

Actual Plugging Report: Ran 1" to 1060 and gelled hole with 20 bbls of gel water then spotted 25 sacks of cement. Pulled 1" TO 700' and spotted with 20 sacks of cement. Pulled 1" out and perforated casing at 350'. Ran 1" to 350' and cemented to surface with 125 sacks of cement. Cement on inside and outside of casing.

**INVOICED**

RECEIVED  
KANSAS CORPORATION COMMISSION

DATE 6-11-08

MAY 29 2008

INV. NO. 008061815

CONSERVATION DIVISION  
WICHITA, KS

Remarks:           
(If additional description is necessary, use BACK of this form.)

I did/did not observe this plugging.

Signed: Mike Heffern  
TECHNICIAN

PUR PRT  
PRT