

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

API Well Number: 15-065-22994-00-02  
 Spot: E2E2NW Sec/Twnshp/Rge: 11-7S-21W  
3880 feet from S Section Line, 2880 feet from E Section Line  
 Lease Name: JEROME Well #: 1  
 County: GRAHAM Total Vertical Depth: 3736 feet

Operator License No.: 33979  
 Op Name: CLIPPER ENERGY LLC  
 Address: TWO TURTLE CRK 3838 OAK LAWN  
DALLAS, TX 75219

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1665		2 SX
CIBP		3370		2 SX
PC		1670		
PKR		1285		PACKER TYPE AND SETTING DEPTH: AD-1 SET @ 1285' WITH A 5 FOOT TAILPIPE.
PROD	5.5	3736	0	182 SX
SURF	8.625	230	0	150 SX
T1	2.875	1285		

121.42

Well Type: SWD UIC Docket No: D30078.0 Date/Time to Plug: 05/20/2008 11:00 AM  
 Plug Co. License No.: 33979 Plug Co. Name: CLIPPER ENERGY LLC  
 Proposal Rcvd. from: TOM BERENS Company: CLIPPER ENERGY LLC Phone: (785) 656-2765

Proposed Plugging Method: Ordered out 175 sxs 60/40 pozmix - 4% gel - 500# hulls.  
 PC at 1670' to 910' w/340 sxs.  
 Squeeze 840' to 580' w/350 sxs - 530' to surface w/150 sxs.  
 Cedar Hills perms: 1290' to 1350'.  
 PBTD 1665' w/25 sxs.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
 Date/Time Plugging Completed: 05/20/2008 4:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 175 sxs down 5 1/2" casing with 600# hulls.  
 Max. P.S.I. 300#. S.I.P. 100#.  
 Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3363	3365		LANSING
1290	1350		CEDARHILL

INVOICED  
 DATE 6-16-08  
 INV. NO. 2008061833

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 JUN 03 2008  
 CONSERVATION DIVISION  
 WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams

MAY 28 2008

CM PKT


CLIPPER ENERGY LLC  
DALLAS TX 75219

#1 JEROME OWWO

11-07S-21W  
1400'FNL & 2400'FWL, SEC  
KANSAS

**City:** GRAHAM **Spot:** NE NE SE NW **API:** 15-065-22994  
**Site:** 4-3/4 N & 1/2 W OF NICODEMUS KS **Lat/Long:** 39.46311 -99.63068  
**Field:** PRUITT SOUTH EXT (1/4 N)

**FR:** 09/13/2007 **Spd:** 10/02/2007 **Drig Cp:** 10/05/2007 **Issued:** 04/14/2008 **Revised:** 04/14/2008



Copyright 2008 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

**IP Status:**

**SWDW, ARB, INTV NA, 2/15/2008**

**Contr:** WARREN DRILLING #14

**Elev:** 2159 GL

**Formation Tops:** (L-Log, S-Sample, D-Driller)

NO TOPS RPTD

RTD OLD

3736 -1577

**Old Info:**

**Well Record:** DENIS F ROBERTS, #33 BENOIT,  
SPD 08/24/2004, DC 08/29/2004, 8-5/8" 230 (ALT  
2), D&A, ARB, 8/29/2004(CARD ISSUED  
05/16/2005)

**Contr:** DISCOVERY DRILLING #1

**Find:**

NO CORES OR DSTS RPTD

**Comp Info:** TRGT ZN: LKC, ARB (OIL), PTD 3900

(ARB), D & A 8/29/2004 - TIGHT HOLE - NO

OTHER INFO AVAILABLE - TEMP COMP

5/16/2005

**New Info:**

**Well Record:** FR 09/13/2007, RE-ENTERED  
10/02/2007, WSH DWN TO 3736, DC 10/05/2007,  
PROD CSG NA

**Find:**

COMMENT: KCC API 15-065-22994-0001; MI &  
RURT 10/2-10/3/2007

**Comp Info:** TRGT ZN: ARB (OIL), PTD 3736  
(ARB), MICT (1/29/2008) - CO, (ARB OH), COMP  
AS SWDW - INJECTION RATE SATISFACTORY,  
2/15/2008 - TIGHT HOLE - NO OTHER INFO  
AVAILABLE - TEMP COMP 4/14/2008