

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20878-00-00
Spot: SESENE Sec/Twnshp/Rge: 18-16S-13W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: BITTER C Well #: 6
County: BARTON Total Vertical Depth: 3453 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3357		
PROD	5.5	3452	0	400 SX
SURF	8.625	355	0	275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2008 10:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: GEORGE STOEPLWERTH Company: DARRAH, JOHN JAY, JR. Phone: (620) 786-4046

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
PC - 807' up to 410' w/225 sxs - did not circulate.
CIBP at 3357' plus 2 sxs cement. PBTB 3345'.
Perfs Lansing 3232' - 3234'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/23/2008 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Copeland rigged to 5 1/2" casing - pumped 50 sxs 60/40 pozmix - 4% gel w/150# hulls mixed in.
Pumped 14 sxs gel with 50# hulls mixed in.
Pumped 200 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in - well went on small vacuum - left set, 45 minutes.
Rigged to 8 5/8" - pumped 25 sxs 60/40 pozmix - 4% gel.
Max. P.S.I. 400#. S.I.P. 400#.
Rigged back onto 5 1/2" casing - pumped 10 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3399	3404		
3232	3234		

INVOICED
DATE 6-16-08
INV. NO. 2008061835

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 03 2008

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #C35503.

Plugged through: CSG

CONSERVATION DIVISION
WICHITA KS

District: 04

Signed *Pat Staab*
(TECHNICIAN)

MAY 28 2008

PS

CITIES SERVICE OIL CO.

#6 BITTER "C"

18-16-13W
SE SE NE

209 E. WILLIAM, WICHITA, KS.

CTY BARTON

CONTR DUKE DRIG. CO.

FIELD TRAPP

GEOL

E 1949 KB c 2/10/75 CARD ISSUED 3/13/75 IP P 35 BOPD + 210 BWPD
ARB 3399-3405

+	+	+
+	+	+
+	+	+

API 15-009-20,878

LOG	TOPS	DEPTH	DATUM
HEEB		3068	-1119
TOR		3087	-1138
LANS		3147	-1198
BKC		3357	-1408
ARB		3371	-1422
LTD		3423	-1474
RTD		3424	-1475

8-5/8" 355/275SX

DST (1) (LANS) 3232-41/30-60-30-30,
REC 30'M, SIP 1062-765#, FP 27-
35#, 35-35#

DST (2) (ARB) 3382-87/30-30-30-60, REC
50' VSOCM, SIP 1016-25#, FP 17-26#,
26-35#

DST (3) (ARB) 3382-94/30-60-30-90, REC
80' GIP, 40' GO, 50' GCM, 620' OCW,
SIP 1068-1068#, FP 26-199#, 199-
328#

MICT - CO & PF (ARB) 10/3399-3405,
SWB DWN & SWB 23 BO + 108 BW/9HRS, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS