

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19333-00-00
Spot: SESWNE Sec/Twnshp/Rge: 10-31S-3E
2951 feet from S Section Line, 1320 feet from E Section Line
Lease Name: SATTERTHWAITE Well #: 1
County: COWLEY Total Vertical Depth: 3039 feet

Operator License No.: 9576
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C
Address: 8135 281ST RD
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3018	987	40 SX
SURF		135		

98.77

Well Type: EOR UIC Docket No: E12927.4 Date/Time to Plug: 04/15/2008 8:00 AM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: BRENT WHITEMAN Company: GEN-DOR OIL CO. Phone: (620) 222-7808

Proposed Plugging Method: FILL WITH SAND TO 50' (2,968') ABOVE OPEN HOLE, DUMP BAIL 5 SACKS CEMENT ON TOP. SHOOT AND PULL PIPE, CIRCULATE CEMENT FROM 350' TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/21/2008 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:
RIH WITH CIBP AND WIRELINE, TAGGED FILL UP @ 2,936'. PULLED UP AND SET CIBP @ 2930'. DUMP BAILED 5 SACKS CEMENT ON TOP. SHOT 5-1/2" CASING @ 987', LAYED DOWN CASING. RIH WITH TUBING @ 350', CONSOLIDATED MIXED & PUMPED 85 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1100, 5-21-2008. CONSOLIDATED CEMENT TICKET #14065.

Perfs:

Top	Bot	Thru	Comments
3018	3039		

INVOICED
DATE 6-16-08
INV. NO. 2008061840

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 27 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: 180' OF TUBING LEFT IN HOLE DURING TOP PLUG
Plugged through: TBG

District: 02

Signed Duane R. Krueger
(TECHNICIAN)

PA