

KCC per
Per Corp.

O:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21474-00-01
Spot: SWNESE Sec/Twnshp/Rge: 21-15S-14W
¹⁶⁸⁸ ~~1650~~ feet from S Section Line, 290 feet from E Section Line
Lease Name: BENDER OWWO 2453 Well #: 1
County: RUSSELL Total Vertical Depth: 3354 feet

Operator License No.: 33554
Op Name: K & B NORTON OIL & INVESTMENTS
Address: 510 W 36TH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3352	0	w/150 sxs cmt
SURF	8.625	332	0	w/200 sxs cmt <u>109.01</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/15/2008 10:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JOEL STULL Company: K&B NORTON OIL & INVESTMEN Phone: (785) 628-3422

Proposed Plugging Method:	Ordered 470 sxs 60/40 pozmix - 4% gel - 900# hulls. Junk in the hole at 1525'. Emergency plugging with rig over the hole. Plug through tubing.
---------------------------	---

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2008 11:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report: _____ Perfs: _____

05/15/2008
Ran tubing to 1500' - tied to tubing - pumped 200 sxs cement.
Pulled tubing to 1200' - pumped 125 sxs cement with 400# hulls.
Pulled to 800' - pumped 50 sxs cement - pulled rest of tubing - stopped for the day.

05/16/2008
Tagged cement at 540' - pulled one joint tubing - pumped 80 sxs cement with 300# hulls - circulated to the top.
Pulled tubing - topped off with 15 sxs cement. S.I.P. 100#.
Pressured up on surface pipe - full of cement.

INVOICED
DATE 6-16-08
INV. NO. 2008061843

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 30 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #34012.
Plugged through: TBG

District: 04 Signed Bruce Rodie
(TECHNICIAN) CM

MAY 27 2008

AKT

ROY VONVELDT
S24 ST. JOHN

#1 BENDER "OWWO"

21-15-14W
SW NE SE

RUSSELL, KS. 67665

CONTR DUKE DRILLING CO., INC. CTY RUSSELL

GEOL

FIELD STRECKER

1825 KB CM 12/7/80 CARD ISSUED 4/23/81 IP P B BO & 14 BWPD
T820 GL LKC 3191-3260

+	+
+	+

API 15-167-21,474

LOG	TOPS	DEPTH	DATUM
HEEB		2977	-1152
LANS		3039	-1214
B KC		3246	-1421
ARB		3301	-1476
RTD		3340	-1515
LTD		3342	-1517
DDTD		3354	-1529

OLD INFO: OPERATOR WAS D R LAUCK OIL CO., INC., #1 BENDER, SPD 6/9/80, SET 8-5/8" 332/200SX, COMPLETED AS D&A/ARB 6/19/80
DST (1) 3045-3086/30-30-30-30, REC 10' DM W/FEW SPKS O, SIP 73-52#, FP 31-42/42-42#
DST (2) 3106-3131/30-45-30-75, REC 90' GIP, 120' THIN M W/SPKS O, 30' MDY W, SIP 429-450#, FP 21-73/73-105#
DST (3) 3180-3218/30-45-30-45, REC 45' GCM W/SPKS O, SIP 105-94#, FP 31-31/52-52#
DST (4) 3215-3245/30-30-30-30, REC 5' DM W/SO, SIP 1125-1125#, FP 31-31/ (OVER)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

ROY VONVELDT

#1 BENDER "OWWO"

21-15-14W
SW NE SE

31-31#
DST (5) 3242-3279/30-45-30-60, REC 60' HO&GCM, 250' SL O&G-MDY WTR, SIP 585-585#, FP 63-115/126-188#
DST (6) 3292-3304/30-30-30-30, REC 15' M W/SCUM O, SIP 74-94#, FP 21-21/32-32#
DST (7) 3297-3309/30-45-30-22, REC 100' M, SIP 377-251#, FP 84-84#
DST (8) 3301-3320/45-45-43-51, REC 5' HO&GCM, 40' MDY W W/SO, 90' MDY WTR, SIP 1066-1066#, FP 11-42/42-84#

CORRECTION: WAS SW NW SE

NEW INFO: RE-ENTERED 12/7/80, WSH DWN
TO OTD, DD 3354' TD, SET 4" 3352,
MIGT - CO, PF (LKC) 3236-60, 3233-35,
3209-12, 3191-95, AC 3500 G (15%),
SWB LD W/GSO, POP. P 14 BO & 20 BWPD