

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20503-00-01  
Spot: NWSWSW Sec/Twnshp/Rge: 9-1S-34W  
990 feet from S Section Line, 4980 feet from E Section Line  
Lease Name: CAHOJ UNIT Well #: 922  
County: RAWLINS Total Vertical Depth: 4355 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4351	0	w/495 sxs cmt
SURF	8.625	335	0	w/190 sxs cmt <u>141.54</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/13/2008 10:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-1031

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 800# hulls - 20 sxs gel.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/13/2008 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 355' w/190 sxs cement.  
5 1/2" production casing set at 4351' w/495 sxs cement.  
PBTD 4311' - TD 4355'.  
Casing scraper stuck in 5 1/2" casing. Top of fish at 3902'.  
Perforated 5 1/2" production casing at 2980' - 1830' - 390'. Casing hole at 3969'.  
Ran tubing to 3835' - pumped 75 sxs cement with 400# hulls.  
Pulled tubing to 3017' - pumped 20 sxs gel at 2600#.  
Pulled tubing to 1855' - pumped 40 sxs cement.  
Pulled tubing to 408' - circulated cement to surface from 5 1/2" production casing and 8 5/8" surface casing with 95 sxs cement.  
Pulled tubing to surface. Cement approximately 10' from surface.

Perfs:

Top	Bot	Thru	Comments
4006	4209		

**INVOICED**  
DATE 6-18-08  
INV. NO. 2008061852

RECEIVED  
KANSAS CORPORATION COMMISSION  
**JUN 03 2008**

Remarks: SWIFT SERVICES, INC.-TICKET #14045.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN) CM

Form CP-2/3

MAY 28 2008

*PKT*

REPLACEMENT CARD

GETTY OIL COMPANY  
3705 VINE, UNIT #4  
HAYS, KS 67501

#922 CAHOJ UNIT

9-1-34W  
990' ESL &  
300' FWL, SW/4

CONTR MURFIN DRILLING COMPANY

CITY RAM INS


GEOLOG

FIELD CAHOJ

ELV 3133 KB SPD 12/5/83

CARD ISSUED 2/24/84

IP P 48 BO & 1047 BWPD  
LRC 4006-4209 OA



API 15-153-20.503

LOG	Type	Depth/Datum
TOP		3806- 873
OREAD		3904- 771
DOUG		3967- 834
LANS		4005- 872
RTD		4355-1222

8 5/8" - 335/190SX, 5 1/2" - 4351/495SX  
NO CORES OR DSTS  
MCT - CO, PF (LKC) 4203-09, 4174-76, 4158-61, 4081-83,  
4023-27, 4019-20 & 4006-11 W/4 SPF, AC 6000G, SWB DWN,  
GSO, T&R, POP, P 48 BO & 1047 BWPD, 2/2/84

INFO RELEASED: 11/22/84 - ADDED WELL INFO FR 9/14/83.

COPYRIGHT 1984  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

8-12-83