

KCC OIL/GAS REGULATORY OFFICE

Date 5-15-08 thru 5-17-08

- New Situation
- Response to Request
- Follow-up

Operator license # 30535

Operator Hartman Q. I.

Address 12950 E 13th
Wichita, Ks 67230

Location Approx CSE, Sec 31, T 21 S, R 33 W

Lease R. Crisit Well # 5

County Finney

Operator phone number 316 636 2090

API # 15-055-20148-00-00

Reason for Investigation: Alternate II Cementing

8 5/8" @ 364', 4 1/2" @ 4705' w/ 250sx, RTD-4735'

Problem: _____

Person(s) Contacted: _____

Findings: Set b.p. @ 1550'. Perf @ 1150'.

Allied pumped 275 sx 60/40 Pa 4% gel 2% cc followed
by 50sx Class A + 2% cc. No blow or circulation upon annulus

5-16-08 Log Tech ran temp survey. Toc @ 900'. Perf 4 holes @ 730'
(Shale between 730' & 900')

5-17-08 Allied pumped 200sx 60/40 Pa 4% gel followed by 50sx Class A amt.
Had nearly full circulation and circulated cement
to surface.

Action/Recommendations: _____

Alt II Cementing Complete

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 29 2008

CONSERVATION DIVISION
WICHITA, KS

- Lease Inspection
- Complaint
- Field Report

By Ken Jehle

PIRT II

Retain 1 copy Joint District Office
Send one copy Conservation Division

- RBDMS
- KGS
- District files
- TA program
- T-1 database
- Courthouse